

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-059-24781-00-00
Spot: SENWNWSE Sec/Twnshp/Rge: 31-17S-21E
2224 feet from S Section Line, 2097 feet from E Section Line
Lease Name: MACDOUGALL Well #: 1
County: FRANKLIN Total Vertical Depth: 536 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	507		80 SX
SURF	6.25	23		3 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/29/2013 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: IF CAN PMP WTR INTO WELL/FM, THEN PMP IN AND FILL PROD CSG W/CMT, PRESS UP ON SAME AND SHUT WELL IN. IF CAN NOT PMP FLUID, FIH W/1" TBG TO BTM, PMP AND FILL PROD CSG W/CMT, POOH 1" TBG, TOP CSG OFF W/CMT, PRESS UP AND SHUT WELL IN. RETURN AT A LATER DATE, CUT CSG OFF BELOW "PLOW DEPTH".

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE
Date/Time Plugging Completed: 05/29/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO TD IN 2-7/8 INCH CASING AND FILL TO SURFACE WITH PORTLAND CEMENT. PULL OUT 1-INCH, TOP OFF, THEN SQUEEZE SHUTTING IN AT 750 PSI. USE TOTAL OF 25 SACKS OF CEMENT.

Perfs:

RECEIVED

JAN 29 2014

KCC Chanute Dist. #3

LS

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
02/11/14

(TECHNICIAN)

KCC WICHITA

Form CP-2/3

JAN 31 2014

RECEIVED