

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-059-24441-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 6-18S-21E
3610 feet from S Section Line, 4500 feet from E Section Line
Lease Name: ROSEBERRY #3 Well #: E-1
County: FRANKLIN Total Vertical Depth: 616 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	615		0 SX
SURF	7	21		0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/26/2013 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: IF CAN PMP WTR INTON WELL/FM, RMP AND FILL PROD CSG W/CMT, PRESS UP ON SAME AND SHUT WELL IN. IF CAN NOT PMP FLUID, RIH 1"TBG TO BTM, PMP AND FILL PROD CSG, POOH 1"TBG, TOP OFF W/CMT, PRESS UP AND SHUT WELL IN, RETURN ATA A LATER DATE, CUT CSG OFF BELOW "FLOW DEPTH".

Plugging Proposal Received By: LEVI SHORT WitnessType: NONE
Date/Time Plugging Completed: 06/26/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO TD IN 2-7/8 INCH CASING AND FILL TO SURFACE WITH PORTLAND CEMENT. PULL OUT 1-INCH, TOP OFF, THEN SQUEEZE SHUTTING IN AT 725 PSI. USE TOTAL OF 24 SACKS OF CEMENT.


Perfs:

Top	Bot	Thru	Comments
574	574		
RECEIVED JAN 29 2014 KCC Chanute Dist. #3 LS			

Remarks:

Plugged through: TBG

District: 03

Signed  (TECHNICIAN)

KCC WICHITA

Form CP-2/3

JAN 31 2014

RECEIVED