

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-059-25064-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 3-17S-21E  
4723 feet from S Section Line, 3579 feet from E Section Line  
Lease Name: COWLES Well #: 3-1  
County: FRANKLIN Total Vertical Depth: 938 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	862		94 SX
SURF	8.625	21		8 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/01/2013 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: RIH 2 3/8" TBG TO BTM, PMP PROD CSG FULL OF "GEL" THEN PMP A 50' CMT PLUG AT TD, PULL UP TBG TO 500', THEN PMP ANOTHER 50' CMT PLUG, PULL UP TBG TO 250' AND FILL PROD CSG TO SURFACE W/CMT, POOH TBG, TOP PROD CSG OFF, PRESS UP ON SAME, AND SHUT WELL IN. RETURN AT A LATER DATE, CUT CSG OFF BELOW "PLOW DEPTH".

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE  
Date/Time Plugging Completed: 07/01/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

PUMP 2 SACKS OF GEL INTO CASING AT TD. PLACE 50 FOOT CEMENT PLUG AT TD, 50 FOOT PLUG AT 500 FEET, AND CEMENT FROM 250 FEET TO SURFACE. USE TOTAL OF 53 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
217	220		
188	192		

RECEIVED  
JAN 29 2014  
KCC Chanute Dist. #3

LS

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]  
02/11/14 (TECHNICIAN)

KCC WICHITA Form CP-2/3

JAN 31 2014

RECEIVED