

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-059-24816-00-00
Spot: NWNW Sec/Twnshp/Rge: 31-17S-21E
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: DAVIS Well #: B-3
County: FRANKLIN Total Vertical Depth: 729 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	700		0 SX
SURF	7	20		0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/26/2013 12:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: () 620-3111

Proposed Plugging Method: IF CAN PMP WTR INTO WELL /FM, THEN PMP IN AND FILL THE PROD CSG W/CMT, PRESS UP ON SAME AND SHUT-IN. IF CAN NOT PMP FLUID, RIH W/1" TBG TO BTM, PMP PROD CSG FULL OF CMT, POOH TBG, TOP PROD CSG OFF W/CMT, PRESS UP AND SHUT WELL IN. RETURN AT A LATER DATE, CUT CSG OFF BELOW "PLOW DEPTH".

Plugging Proposal Received By: LEVI SHORT Witness Type: NONE
Date/Time Plugging Completed: 06/26/2013 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO TD IN 2-7/8 INCH CASING AND FILL TO SURFACE WITH PORTLAND CEMENT. PULL OUT 1-INCH, TOP OFF, THEN SQUEEZE SHUTTING IN AT 750 PSI. USE TOTAL OF 21 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
551	561		
401	422		

RECEIVED

JAN 29 2014

KCC Chanute Dist. #3

LS

Remarks:

Plugged through: TBG

District: 03

Signed [Signature]
02/01/14 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

JAN 31 2014

RECEIVED