

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-205-01140-00-00  
Spot: NWENWSE Sec/Twnshp/Rge: 29-30S-16E  
2370 feet from S Section Line, 1870 feet from E Section Line  
Lease Name: UNIT 1 - ELLIS Well #: ELLIS #2  
County: WILSON Total Vertical Depth: 818 feet

Operator License No.: 3830  
Op Name: A X & P, INC.  
Address: PO BOX 1176  
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2	790		10 SX
PROD	5	800		
SURF	12	30		10 SX
SURF	8	40		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/08/2013 8:00 AM  
Plug Co. License No.: 33969 Plug Co. Name: HOUSEL, RICK DBA RICK'S WELL SERVICE  
Proposal Rcvd. from: J J HANKE Company: A X & P, INC Phone: (620) 325-5212

Proposed Plugging Method: Perf. Casing @700' and @60' RIH 1" pipe to TD and cement up. Top off w. cement.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 11/11/2013 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The casing was perforated at 600', 250' and 75'. A 1" cement string was run to 800'. Gel was then circulated and then 25 sacks of cement spotted. The 1" cement string was pulled to 600' and 20 sacks of cement spotted. The rig was shut down overnight. A 1" cement string was then lowered to 250' and the well pumped full of cement using 63 sacks. A total of 108 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
800	812		

RECEIVED  
JAN 30 2014  
KCC Chanute Dist. #3  
AD

Remarks:

Plugged through: CSG

District: 03

Signed [Signature]  
02/11/14  
(TECHNICIAN)  
KCC WICHITA  
FEB 03 2014  
RECEIVED