

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-19679-00-00
Spot: SWSWNWNW Sec/Twnshp/Rge: 12-22S-10E
4240 feet from S Section Line, 5119 feet from E Section Line
Lease Name: DEMALORIE SOWDER Well #: S-6
County: GREENWOOD Total Vertical Depth: 3475 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1229		
PROD	8	2660		636 SX
SURF	13	147		75 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 10/15/2013 12:00 PM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Rcvd. from: DWAIN STOUT Company: _____ Phone: (316) 640-9072

Proposed Plugging Method: Dump 50 ft of sand on bottom. Run tubing to top of sand and spot 50 ft of cement. Pull tubing to bottom of perforations and cement to top of perforations. Pull tubing to 150 ft and cement to surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL
Date/Time Plugging Completed: 10/16/2013 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

pumped 20 sxs cement @ 2470' thru tubing, pulled tubing out pushed rubber plug to 1070'
pumped 20 sxs cement, pulled tubing to 150' pumped 60 sxs cement to surface.

Perfs:

Top	Bot	Thru	Comments
1110	1150		

RECEIVED
FEB 03 2014
KCC Chanute Dist. #3
MH

Remarks:

Plugged through: TBG

District: 03

KCC WICHITA
FEB 06 2014
RECEIVED

Signed Mike Duff
02/10/14 (TECHNICIAN)