

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-10112-00-00
Spot: SENE Sec/Twnshp/Rge: 35-33S-31W
3290 feet from S Section Line, 620 feet from E Section Line
Lease Name: SIMONSON A Well #: 3
County: SEWARD Total Vertical Depth: 5962 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4150		WITH 5 SX CMT
DVT		4399		WITH 200 SX CMT
PROD 7		5952	2520	WITH 400 SX CMT
SURF	9.625	1535		WITH 700 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/29/2014 12:30 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 5745' WITH 5 SX CMT. PLUG AT 1570' WITH 80 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 01/29/2014 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

TOP OF FISH @ 4275'. SET CIBP @ 4150' WITH 5 SX CMT. LOADED HOLE WITH MUD. 1ST PLUG AT 1570' WITH 80 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5795	5908		

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

District: 01

RECEIVED

JAN 31 2014

KCC DODGE CITY

Signed

Eric MacLaren
1/29/14

(TECHNICIAN)

KCC WICHITA

FEB 07 2014

RECEIVED

Form CP-2/3

part