

3 020628

15-001-70034-0000 221 R
10-13 15.001.03353.00.00

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Probably drilled in 1950's

NE/4, SEC. 18, T. 26 S, R. 18 W/E

2710 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101 STATE CORPORATION COMMISSION Lease Name Enaker Well # OW #1

Operator: State of Kansas JAN 24 1990 County Allen

Name & Address Fee Fund Plugging CONSERVATION DIVISION Well Total Depth Approximately 800' feet

Wichita, Kansas Conductor Pipe: Size feet

Surface Casing: Size 9" feet N/A

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kephart Drilling Inc. License Number 5379

Address R.R. #1, Box 68A, Thayer, Kansas 66776

Company to plug at: Hour: 8:00 am Day: 5 Month: 10 Year: 19 89

Plugging proposal received from Clayton P. Titel

(company name) Kansas Corporation Commission (phone) 316-431-6946

were: This well consisted of 1 1/2" to 2" casing set at approximately 800' that
had been cemented in at TD only. A previous attempt to plug this well had
left some cement in the well at approximately 325' and a plugging packer
in the casing at approximately 320'. Additionally the top 50' of casing had
been parted and evidently removed at some time in the past.

Plugging Proposal Received by Clayton P. Titel (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 5:00 pm Day: 13 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 4 1/2" casing on a rag packer was set inside the 9" surface
casing and cemented in. 3/4" pipe was ran into the old 1 1/2" to 2" casing.
to 320'. 1" pipe was ran to 325' outside the 1 1/2" to 2" casing. Cement
was circulated through the 3/4" pipe to surface and then cement was circulated
to surface through the 1" pipe. The 1" and 3/4" pipe were removed. Cement
was pumped into the 4 1/2" casing until it held 300 PSI, and the well was shut

Remarks: in.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Clayton P. Titel (TECHNICIAN)