

3020702

15-001-03356-00-0906

7-10

~~15-001-70549-0000~~

R

TO:

STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION

200 COLORADO DERBY BUILDING

WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 101OPERATOR: STATE OF KANSASNAME AND FEE FUND PLUGGING

ADDRESS _____

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR K.W. OIL WELL SERVICE LICENSE NUMBER 8933ADDRESS P.O. BOX 15, THAYER, KANSAS 66776COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 10 MONTH: 7 YEAR: 90PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL(COMPANY NAME) KCC (PHONE) 316-431-6946

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HAD BEEN EVIDENTLY CEMENTED IN AT TD
ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY CLAYTON TITELPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____OPERATIONS COMPLETED: HOUR: 6:00 PM DAY: 10 MONTH: 7 YEAR: 90

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN TO 432' INSIDE THE 2" CASING. 1" PIPE WAS RAN TO 400' IN THE 2"
AND 8" ANNULUS. BOTH STRINGS OF PIPE ENCOUNTERED OBSTRUCTIONS AT THOS DEPTHS. CEMENT WAS PUMPED INTO THE
3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" AND 3/4" ANNULUS AT SURFACE. CEMENT WAS PUMPED INTO THE 1"
UNTIL CEMENT CIRCULATED FROM THE 2" AND 8" ANNULUS AT SURFACE. BOTH THE 3/4" AND 1" PIPE WERE THEN REMOVED.
THE 2" CASING WAS THEN CAPPED, SQUEEZED TO 100 PSI AND SHUT IN. 117 SACKS OF CEMENT WERE PUMPED INTO THIS
WELL BY CONSOLIDATED OIL WELL SERVICES, INC.

REMARKS: _____

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED Clayton P. Titel RECEIVED
STATE CORPORATION COMMISSION (TECHNICIAN)

FORM CP-2/3

OCT 1 1990

CONSERVATION DIVISION
Wichita, Kansas