

3 020703

~~15-001-90551-00-00~~
7-11

107

15.001.03354.00.00

R

TO:

STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION

200 COLORADO DERBY BUILDING

WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # _____

OPERATOR: STATE OF KANSASNAME AND FEE FUND PLUGGING

ADDRESS _____

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR K.W. OIL WELL SERVICE LICENSE NUMBER 8933ADDRESS P.O. BOX 15, THAYER, KANSAS 66776COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 11 MONTH: 7 YEAR: 90PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL(COMPANY NAME) KCC (PHONE) 316-431-6946

WERE: THIS WELL PROBABLY CONSISTED OF 2" CASING TO APPROXIMATELY 850' THAT HAD BEEN CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO RUN PIPE TO AS DEEP A DEPTH AS POSSIBLE INSIDE AND OUTSIDE THE 2" CASING AND CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY CLAYTON TITELPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____OPERATIONS COMPLETED: HOUR: 6:00 PM DAY: 11 MONTH: 7 YEAR: 90

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN TO 600' INSIDE THE 2" CASING. 1" PIPE WAS RAN TO 500' IN THE 2" AND 10" ANNULUS. CEMENT WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" AND 3/4" ANNULUS AT SURFACE. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" AND 10" ANNULUS AT SURFACE. THE 3/4" AND 1" PIPE WERE THEN REMOVED. THE 2" CASING WAS CUT OFF, THE 10" CAPPED, SQUEEZED TO 50 PSI AND SHUT IN. 160 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

REMARKS: _____

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
STATE CORPORATION COMMISSION (TECHNICIAN)

FORM CP-2/3

OCT 1 1990

CONSERVATION DIVISION
Wichita, Kansas