

3020872

15.001.13027.00.00 146 R

2-7

15.001.03351.00.00

TO:

API NUMBER 15- N/A

STATE CORPORATION COMMISSION

NE, SEC. 18, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

3740 FEET FROM SOUTH SECTION LINE

200 COLORADO DERBY BUILDING

1540 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME FRAKER WELL # OW6

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE #

WELL TOTAL DEPTH APPROXIMATELY 850 FEET

OPERATOR: STATE OF KANSAS

CONDUCTOR PIPE: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 8 FEET N/A

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR WAY DRILLING COMPANY LICENSE NUMBER 6674

ADDRESS ROUTE 1, BOX 82, HUMBOLDT, KS 66748

COMPANY TO PLUG AT: HOUR: DAY: MONTH: YEAR:

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: THIS WELL CONSISTED OF 2" CEMENT LINED CASING TO APPROXIMATELY 800' THAT HAD EVIDENTLY BEEN

CEMENTED IN AT TO ONLY. THE PLUGGING PROPOSAL WAS TO FILL AS MUCH OF THE WELL AS POSSIBLE WITH CEMENT

INSIDE AND OUTSIDE THE 2" CASING.

PLUGGING PROPOSAL RECEIVED BY CLAYTON TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 7 MONTH: 2 YEAR: 92

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN TO 693' INSIDE THE 2" CASING. 1" PIPE WAS RAN TO 700' IN THE 1"

AND 8" ANNULUS. CEMENT WAS PUMPED INTO BOTH THE 3/4" AND 1" PIPE UNTIL THE WELL WAS CIRCULATED FULL OF

CEMENT INSIDE THE 2" AND IN THE 2" AND 8" ANNULUS FROM 700' TO SURFACE. THE 3/4" AND 1" WERE THEN REMOVED.

A CAP WAS WELDED ONTO THE 8" SURFACE CASING AND THE WELL WAS SQUEEZED TO 50 PSI AND SHUT IN. CEMENT WAS

PUMPED BY CONSOLIDATED WELL SERVICES INC.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1992
CONSERVATION DIVISION
Wichita, Kansas