

3020881

2-27

15.001.03348.00.00

API NUMBER 15- N/A

TO:

STATE CORPORATION COMMISSION

NE, SEC. 18, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

4730 FEET FROM SOUTH SECTION LINE

200 COLORADO DERBY BUILDING

1420 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME FRAKER WELL # OW 8

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE #

WELL TOTAL DEPTH APPROXIMATELY 850 FEET

OPERATOR: STATE OF KANSAS

CONDUCTOR PIPE: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 10 FEET N/A

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR WAY DRILLING COMPANY LICENSE NUMBER 6674

ADDRESS ROUTE 1, BOX 82, HUMBOLDT, KS 66748

COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 26 MONTH: 2 YEAR: 92

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: VISIBLE AT SURFACE ON THIS WELL WAS WATER FILLED SURFACE CASING. THE PLUGGING PROPOSAL WAS TO
WASH 2" TUBING TO AS DEEP A DEPTH AS POSSIBLE AND CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY CLAYTON TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 27 MONTH: 2 YEAR: 92

ACTUAL PLUGGING REPORT 2" TUBING WAS WASHED INTO THIS WELL TO 350'. AT THAT DEPTH A SOLID OBSTRUCTION WAS
ENCOUNTERED. CEMENT WAS PUMPED INTO THE 2" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" AND 10" ANNULUS AT
SURFACE. THE 2" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. 127 SACKS OF CEMENT
WERE PUMPED INTO THIS WELL BY CONSOLIDATED OIL WELL SERVICES INC.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1992
CONSERVATION DIVISION
Wichita, Kansas