

3020954

6-22
15.001.03350.00.00
2R

TO:

STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION

200 COLORADO DERBY BUILDING

WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # _____

OPERATOR: STATE OF KANSAS _____

NAME AND FEE FUND PLUGGING _____

ADDRESS _____

ABANDONED OIL WELL ☒ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR WAY DRILLING COMPANY _____ LICENSE NUMBER 6674

ADDRESS ROUTE 1, BOX 82, HUMBOLDT, KS 66748

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 22 MONTH: 6 YEAR: 93

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: THIS WELL CONSISTED OF 2" CEMENT LINED CASING PROBABLY TO APPROXIMATELY 800' THAT HAD PROBABLY BEEN CEMENTED IN FROM TD TO 440'. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND OUTSIDE THE 2" CASING.

PLUGGING PROPOSAL RECEIVED BY CLAYTON P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL ☒ PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 22 MONTH: 6 YEAR: 93

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN TO 735' INSIDE THE 2" CASING. 1" PIPE WAS RAN TO 440' IN THE 2" AND 8" ANNULUS. AT 440' A SOLID OBSTRUCTION WAS ENCOUNTERED. 20 SACKS OF CEMENT WERE PUMPED INTO THE 3/4" PIPE. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. BOTH THE 1" AND 3/4" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. 225 SACKS OF CEMENT WERE PUMPED INTO THIS WELL BY CONSOLIDATED OIL WELL SERVICES, INC.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

RECEIVED P. Titel
STATE CORPORATION COMMISSION TECHNICIAN

FORM CP-2/3

JUN 29 1993

CONSERVATION DIVISION
Wichita, Kansas