

3020880

~~15.001.13030.00.00~~ 143 R
2-27
15.001.03349.00.00

TO:

API NUMBER 15- N/A

STATE CORPORATION COMMISSION

NE , SEC. 18 , T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

~~2805~~ 7485 FEET FROM SOUTH SECTION LINE

200 COLORADO DERBY BUILDING

~~2475~~ 1405 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME FRAKER WELL # OW 9

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE #

WELL TOTAL DEPTH APPROXIMATELY 850 FEET

OPERATOR: STATE OF KANSAS

CONDUCTOR PIPE: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 10 FEET N/A

ADDRESS

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR WAY DRILLING COMPANY LICENSE NUMBER 6674

ADDRESS ROUTE 1, BOX 82, HUMBOLDT, KS 66748

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 26 MONTH: 2 YEAR: 92

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: VISIBLE AT SURFACE ON THIS WELL WAS WATER FILLED 10" SURFACE CASING. THE PLUGGING PROPOSAL WAS TO WASH 2" PIPE INTO THE 10" TO AS DEEP A DEPTH AS POSSIBLE AND CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY CLAYTON TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 27 MONTH: 2 YEAR: 92

ACTUAL PLUGGING REPORT 2" TUBING WAS WASHED INTO THE WELL TO APPROXIMATELY 500' AT WHICH A SOLID OBSTRUCTION WAS ENCOUNTERED. CEMENT WAS PUMPED INTO THE 2" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" AND 10" ANNULUS AT SURFACE. THE 2" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. THE SURFACE CASING WAS CAPPED, SQUEEZED TO 50 PSI, AND SHUT IN. 200 SACKS OF CEMENT WERE PUMPED INTO THIS WELL BY CONSOLIDATED OIL WELL SERVICES, INC.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1992
CONSERVATION DIVISION
Wichita, Kansas