

3 020627

15.001.03339.00.00
10-K3

222

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Probably drilled in 1930's

SE/4, SEC. 18, T 26 S, R 18 W/E

1220 feet from S section line

1100 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name Burtiss Well # OW-1

Operator: State of Kansas

County Allen

Name: _____

Address Fee Fund Plugging

Well Total Depth Approx. 800' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 9" feet N/A

Abandoned Oil Well ☒ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kephart Drilling Inc. License Number 5379

Address R.R. #1, Box 68A, Thayer, Kansas 66776

Company to plug at: Hour: 8:00 am Day: 3 Month: 10 Year: 19 89

Plugging proposal received from Clayton P. Titel

(company name) Kansas Corporation Commission (phone) 316-431-6946

were: This well probably consisted of 1 1/2" to 2" casing seated at approximately

800' that had been cemented in at TD only. The casing had evidently parted

at approximately 150' and the top 150' of casing was probably removed from

the well. The plugging proposal was to fill as much of the well as possible

with cement.

Plugging Proposal Received by Clayton P. Titel

(TECHNICIAN) JAN 24 1990

Plugging Operations attended by Agent?: All ☒ Part _____ None _____

Operations Completed: Hour: 10:00 am Day: 13 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT A 7" swedge on 2 7/8" tubing was used to overshoot the casing

at 150'. 3/4" pipe was ran to 940' inside the casing. 1" pipe was ran to 625'

outside the casing. It was determined that the remaining casing was so

deteriorated that the 3/4" pipe was unnecessary. The 3/4" and 2 7/8" pipe were

removed. Cement was pumped into the 1" pipe until cement circulated from the

1" and 9" annulus at surface. The 1" pipe was removed. Approx. 200 sacks of

Remarks: cement were pumped into this well by Consolidated Oil Well Services Inc.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed

Clayton P. Titel
(TECHNICIAN)