

3020731

~~15.001.70075.00.00~~

10-26

15.001.03345.00.00

142
R

TO:

STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION

200 COLORADO DERBY BUILDING

WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # _____

OPERATOR: STATE OF KANSASNAME AND FEE FUND PLUGGING

ADDRESS _____

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR K.W. WELL SERVICES LICENSE NUMBER 8933ADDRESS P.O. BOX 15, THAYER, KANSAS 66776COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 25 MONTH: 10 YEAR: 90PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL(COMPANY NAME) KCC (PHONE) 316-431-6946

WERE: THIS WELL CONSISTED OF 2" CASING PROBABLY SET TO APPROXIMATELY 850' THAT HAD EVIDENTLY BEEN CEMENTED IN AT TO ONLY. THE PLUGGING PROPOSAL WAS TO FILL AS MUCH OF THE WELL AS POSSIBLE WITH CEMENT BOTH INSIDE AND OUTSIDE THE 2" CASING.

PLUGGING PROPOSAL RECEIVED BY CLAYTON TITELPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 26 MONTH: 10 YEAR: 90

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN TO 750' INSIDE THE 2" CASING. 1" PIPE WAS RAN TO 485' IN THE 2" AND 8" ANNULUS. CEMENT WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 3/4" AND 2" ANNULUS AT SURFACE. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" AND 8" ANNULUS AT SURFACE. BOTH THE 3/4" AND 1" PIPE WAS REMOVED. SETTLAGE WAS FILLED FROM SURFACE. A-CAP WAS WELDED ON! ONTO THE SURFACE CASING, THE WELL WAS SQUEEZED TO 50 PSI AND SHUT IN.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)CONSERVATION DIVISION
WICHITA, KANSAS

FORM CP-2/3