

3020955

6-18 15.001.70524.00.00
15.001.03334.00.00

3R

TO: API NUMBER 15- PROBABLY DRILLED IN 1960'S
STATE CORPORATION COMMISSION SE, SEC. 18, T 26 S, R 18 E
CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE
200 COLORADO DERBY BUILDING 2310 FEET FROM EAST SECTION LINE
WICHITA, KANSAS 67202 LEASE NAME BURTISS WELL # OW 8
TECHNICIAN'S PLUGGING REPORT COUNTY ALLEN
OPERATOR LICENSE # _____ WELL TOTAL DEPTH APPROX. 800' FEET
OPERATOR: STATE OF KANSAS CONDUCTOR PIPE: SIZE _____ FEET
NAME AND FEE FUND PLUGGING SURFACE CASING: SIZE NONE FEET
ADDRESS _____
ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____
OTHER WELL AS HEREINAFTER INDICATED _____
PLUGGING CONTRACTOR WAY DRILLING COMPANY LICENSE NUMBER 6674
ADDRESS ROUTE 1, BOX 82, HUMBOLDT, KS 66748
COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 17 MONTH: 6 YEAR: 93
PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL
(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946
WERE: THIS WELL HAS NO SURFACE CASING. THE WELL PROBABLY CONSISTS OF 4 1/2" CASING TO APPROXIMATELY
800' THAT HAD BEEN CEMENTED IN FROM TD TO 250'. THE PLUGGING PROPOSAL WAS TO PERFORATE THE 4 1/2" AT 230'
AND 180', CIRCULATE THE 4 1/2" FULL OF CEMENT, AND SQUEEZE THE BACKSIDE OF THE 4 1/2" FULL OF CEMENT FROM
230' TO SURFACE.
_____ PLUGGING PROPOSAL RECEIVED BY CLAYTON P. TITEL
PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____
OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 18 MONTH: 6 YEAR: 93
ACTUAL PLUGGING REPORT THE 4 1/2" CASING WAS BOND LOGGED. THE 4 1/2" CASING WAS PERFORATED AT 180' AND
230'. 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 725'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT
CIRCULATED FROM THE 1" AND 4 1/2" ANNULUS AT SURFACE. CEMENT ALSO CIRCULATED OUTSIDE THE 4 1/2" AT SURFACE.
AT THIS TIME. THE 1" WAS REMOVED. THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 4 1/2" AND MORE CEMENT
PUMPED TO IMPROVE THE CEMENT OUTSIDE THE 4 1/2". THE 4 1/2" WAS THEN CAPPED. 80 SACKS OF CEMENT
PUMPED INTO THIS WELL BY CONSOLIDATED OIL WELL SERVICES, INC.

REMARKS: _____
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
Wichita, Kansas
(TECHNICIAN)

FORM CP-2/3