

3020712

15.001.03338.00.00 112

7-12

~~15.001.10555.00.00~~

TO: API NUMBER 15- PROBABLY DRILLED 1930'S TO 1950'S
STATE CORPORATION COMMISSION SE , SEC. 18 , T 26 S, R 18 E
CONSERVATION DIVISION - PLUGGING SECTION 1760 FEET FROM SOUTH SECTION LINE
200 COLORADO DERBY BUILDING 1760 FEET FROM EAST SECTION LINE
WICHITA, KANSAS 67202 LEASE NAME BURTISS WELL # OW 3
TECHNICIAN'S PLUGGING REPORT COUNTY ALLEN
OPERATOR LICENSE # WELL TOTAL DEPTH APPROXIMATELY 850 FEET
OPERATOR: STATE OF KANSAS CONDUCTOR PIPE: SIZE FEET
NAME AND FEE FUND PLUGGING SURFACE CASING: SIZE 10" FEET N/A
ADDRESS
ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A
OTHER WELL AS HEREINAFTER INDICATED
PLUGGING CONTRACTOR K.W. WELL SERVICES LICENSE NUMBER 8933
ADDRESS P.O. BOX 15, THAYER, KANSAS 66776
COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 9 MONTH: 7 YEAR: 90
PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL
(COMPANY NAME) KCC (PHONE) 316-431-6946
WERE: THIS WELL EVIDENTLY CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 800' THAT HAD EVIDENTLY BEEN CEMENTED
IN FROM TD TO 85'. THE PLUGGING PROPOSAL WAS TO FILL AS MUCH OF THE 4 1/2" CASING AS POSSIBLE FULL OF
CEMENT.
PLUGGING PROPOSAL RECEIVED BY CLAYTON P. TITEL
PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE
OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 12 MONTH: 7 YEAR: 90
ACTUAL PLUGGING REPORT 1" PIPE WAS RAN TO 700' INSIDE THE 4 1/2" CASING. 3/4" PIPE WAS WASHED TO 85' IN
4 1/2" AND 10" ANNULUS AT WHICH POINT WHAT WAS EVIDENTLY CEMENT WAS ENCOUNTERED. CEMENT WAS PUMPED INTO THE
1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT SURFACE. CEMENT WAS PUMPED INTO THE 3/4" PIPE
UNTIL CEMENT CIRCULATED FROM THE 4 1/2" AND 10" ANNULUS AT SURFACE. THE 1" AND 3/4" PIPE WERE THEN REMOVED
THE WELL WAS THEN CAPPED, SQUEEZED TO 50 PSI AND SHUT IN. 90 SACKS OF CEMENT WERE USED TO PLUG THIS WELL.

REMARKS: (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

RECEIVED
STATE CORPORATION COMMISSION

OCT 1 1990

CONSERVATION DIVISION
Wichita, Kansas

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3