

3020873

15.001.03028.00.00 147 R
2-28
15.001.03347.00.00

TO:

STATE CORPORATION COMMISSION

CONSERVATION DIVISION - PLUGGING SECTION

200 COLORADO DERBY BUILDING

WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # _____

OPERATOR: STATE OF KANSASNAME AND FEE FUND PLUGGING

ADDRESS _____

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR WAY DRILLING COMPANY LICENSE NUMBER 6674ADDRESS ROUTE 1, BOX 82, HUMBOLDT, KS 66748COMPANY TO PLUG AT: HOUR: 2:30 PM DAY: 7 MONTH: 2 YEAR: 92PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946WERE: THIS WELL CONSISTED OF 2" CEMENT LINED TUBING, INSIDE 6 1/4" CASING, INSIDE 8" SURFACE CASING.THE 2" TUBING AND 6 1/4" CASING WERE BOTH IN POOR CONDITION AND PROBABLY CEMENTED AT TD ONLY. THE PLUGGINGPROPOSAL WAS TO REMOVE AS MUCH 2" AND 6 1/4" AS POSSIBLE, INSTALL 50' OF 4 1/2" SURFACE CASING, CIRCULATEFULL OF CEMENT AND SQUEEZE THE WELL.PLUGGING PROPOSAL RECEIVED BY CLAYTON TITELPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART _____ NONE _____OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 28 MONTH: 2 YEAR: 92ACTUAL PLUGGING REPORT THE 2" CEMENT LINED CASING WAS SHOT OFF AT 700'. WHILE PULLING THE 2" THE BOTTOMAPPROXIMATELY 240' FELL OFF INTO THE WELL AND WAS LOST. 460' OF 2" WERE REMOVED. THE 6 1/4" CASING WAS SHOTOFF AT 448' AND 448' OF 6 1/4" WERE REMOVED. 4 1/2" WAS RAN TO 55' AND CEMENTED IN ON A RAG PACKER. 1"PIPE WAS RAN INTO THIS WELL TO 450'. CEMENT WAS PUMPED INTO THE 1" UNTIL CEMENT CIRCULATED FROM THE4 1/2" SURFACE CASING AT SURFACE. THE 1" WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE.THE 4 1/2" SURFACE CASING WAS CAPPED, SQUEEZED TO 275 PSI AND THE WELL WAS THEN SHUT IN. CEMENT WAS PUMPEDREMARKS: BY CONSOLIDATED OIL WELL SERVICES, INC. AN ESTIMATED 340' OF CEMENT LINED 2" AND ANOTHER 360' OF6 1/4" WERE LEFT IN THE BOTTOM OF THIS WELL.(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)
I (DID/XXXXXX) OBSERVE THIS PLUGGING. SIGNED Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3