

2-17 ~~15.001.73038.00.00~~ 4
15.001.03336.00.00

API NUMBER 15- PROBABLY DRILLED IN 1950'S

SE , SEC. 18 , T 26 S. R 18 E

905 FEET FROM SOUTH SECTION LINE

2005	FEET FROM EAST	SECTION	LINE
------	----------------	---------	------

LEASE NAME BURTISS WELL # OW 10 (11)

COUNTY ALLEN

WELL TOTAL DEPTH APPROXIMATELY 800 FEET

CONDUCTOR PIPE: SIZE _____ FEET

SURFACE CASING: SIZE 8 FEET N/A

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR WAY DRILLING COMPANY LICENSE NUMBER 6674

ADDRESS ROUTE 1, BOX 82, HUMBOLDT, KS 66748

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 13 MONTH: 10 YEAR: 94

PLUGGING PROPOSAL RECEIVED FROM CLAYTON P. TITEL

(COMPANY NAME) KANSAS CORPORATION COMMISSION (PHONE) 316-431-6946

WERE: THIS WELL CONSISTED OF 2" CASING PROBABLY TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN FROM TD
TO APPROXIMATELY 675'. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF
CEMENT INSIDE AND OUTSIDE THE 2" CASING.

PLUGGING PROPOSAL RECEIVED BY CLAYTON P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 17 MONTH: 2 YEAR: 95

ACTUAL PLUGGING REPORT 3/4" PIPE WAS RAN INTO THE 2" CASING TO 585' AT WHICH DEPTH A SOLID

OBSTRUCTION WAS ENCOUNTERED. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 700' AT WHICH POINT A SOLID

OBSTRUCTION WAS ENCOUNTERED. 20 SACKS OF CEMENT WERE PUMPED INTO THE 3/4" PIPE. CEMENT WAS PUMPED INTO

THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" AND 8" ANNULUS AT SURFACE. CEMENT WAS PUMPED INTO THE 3/4"

UNTIL CEMENT CIRCULATED FROM THE 2" AT SURFACE. BOTH THE 3/4" AND 1" PIPE WERE REMOVED. SETTLAGE AND

DISPLACEMENT WERE FILLED FROM SURFACE. 277 SACKS OF CEMENT WERE PUMPED INTO THIS WELL BY CONSOLIDATED

REMARKS: INDUSTRIAL SERVICES.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING. *AK*

SIGNED

Clayton P. Titell
(TECHNICIAN)

RECEIVED FOR
STATE CORPORATIONS COMMISSION

FORM CP-2/3

MAR 09 1995

CONSENSUS DIVISION
WICHITA, KANSAS