

15-007-01142-0000
STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER May 6, 1958 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Bristol Resources Corporation OPERATOR'S LICENSE NO. 03048 7-92

ADDRESS 6655 South Lewis, Suite 200, Tulsa, OK 74136 PHONE # (918) 492-7900

LEASE (FARM) Davis Ranch WELL NO. A-1 WELL LOCATION SE NW COUNTY Barber

SEC. 28 TWP. 33S RGE. 14W (E) or (W) TOTAL DEPTH 4640 PLUG BACK TO 4639'

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. 2-26-92

SURFACE CASING SIZE 8.625" SET AT 800' CEMENTED WITH 600 SACKS

CASING SIZE 4.500" SET AT 4639' CEMENTED WITH Unknown SACKS

PERFORATED AT 4586 - 4626

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Plug back to 4536' with sand, spot or dump 4 sx cement; cut and recover 4-1/2" casing; bullhead down surface casing with 300# hulls, 10 sx gel, 70 sx cement, 100# hulls, casing wiper plug and 100 sx cement.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Not Avail. IS ACO-1 FILED? N/A
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN To be determined

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Dan Abney PHONE # (918) 492-7900

ADDRESS 6655 South Lewis, Suite 200, Tulsa, OK 74136

PLUGGING CONTRACTOR Clark Oilfield Service LICENSE NO. 5105 6-92

ADDRESS Medicine Lodge, Kansas PHONE # (316) 886-5665

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Dan R Abney
(Operator or Agent)

DATE: February 21, 1992

①



Kansas Corporation Commission

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

February 26, 1992

Bristol Resources Corp
6655 S Lewis 200
Tulsa OK 74136

Davis Ranch A-1
SE NW
Sec. 28-33-14W
Barber County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238