


15-007-01024-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County. Sec. 3 Twp. 34 Rge. (E) 12 (W)
Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Pickrell Drilling Company
Lease Name Hutchison Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed 10/18/56 19
Application for plugging filed 10/18/56 19
Application for plugging approved 10/18/56 19
Plugging commenced 10/18/56 19
Plugging completed 10/18/56 19
Reason for abandonment of well or producing formation D & A



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production -- -- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation 11670 Depth to top Bottom Total Depth of Well 1767 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	200	8 5/8"	200'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 200', bridge hole and cemented
with 20 sacks cement. Then heavy mud to 20' below cellar,
bridge hole and cement with 10 sacks to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
10-24-56
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
PICKRELL DRILLING COMPANY
705 Fourth Nat'l Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of October, 19 56

My commission expires July 30, 1958 [Signature] Notary Public.

PLUGGING
FILE SEC 3 T. 34 R. 12W
BOOK PAGE 109 LI. E. 24

ROTARY DRILLING LOG

COMPANY: **Pickrell Drilling Company, etal.**
Wichita, Kansas

Rotary Drilling Commenced 10/3/56

LOCATION: **SW SW SW Sec. 3-34-12W Barber County, Kansas**
Hutchison #1

Rotary Drilling Completed 10/18/56

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: **200' (5 jts.) 8 5/8" 22.7# Armco Spiralwld Casing set at 200' with 150 sacks cement circulated.**

Filled with heavy mud to 200', bridge hole and cemented with 20 sacks cement. Then heavy mud to 20' below cellar, bridge hole and cement with 10 sacks to bottom of cellar.

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing.)

Red Rock	200	Circ. for samples at 3580
Shale	615	4695
Red Bed, Shale & Shells	1305	4767
Salt, Shale & Shells	1380	
Shale, Shells & Lime	1695	
Lime	1875	
Lime & Shale	2030	
Lime	2510	
Lime & Shale	3050	
Lime	3367	
Lime & Shale	3486	
Shale & Sand	3765	
Shale & Lime	3988	
Lime	4757	
Mississippi	4767 T.D.	

S.L.M. at 2500 - O.K.
 3000 - O.K.
 4000 - O.K.

Slope Test at 2900 - 0° off
 3500 - 0° off
 4000 - 0° off

RECEIVED
 NOV - 1 1956
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC. 3 T. 34 R. 12W
 BOOK PAGE 119 LINE 24

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By [Signature]
 Attorney-in-Fact

STATE OF KANSAS, }
 COUNTY OF SEDGWICK } ss.:

On this 25 day of October, 1956, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: July 30, 1958

[Signature]
 Notary Public