

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 6 Twp. 34 Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE

Lease Owner Aylward Drilling Company

Lease Name Donovan "C" Well No. 1

Office Address 909 First National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed August 23, 1956

Application for plugging filed June 27, 1967

Application for plugging approved June 28, 1967

Plugging commenced July 10, 1967

Plugging completed August 2, 1967

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production June 29, 1967

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving

Producing formation Mississippian Depth to top 4744 Bottom Total Depth of Well 4821 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	189'	None
				5 1/2"	4821'	2876'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back to 4810  
 Dump chat from 4810 to 4738  
 Cement 5 sacks From 4738 to 4705  
 Ripped pipe at 4000 and 3500- 3000 - 2876  
 Pulled 5 1/2"  
 Bailed hole soen Build wood bridge at 200  
 Rock From 200 to 190  
 Cement 25 sacks From 190 to 125  
 Mud From 125 to 40  
 Rock From 40 to 30  
 Cement 10 sacks From 30 to top

STATE CORPORATION COMMISSION  
 AUG 21 1967  
 8-21-67  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Oilfield Service, Inc.

Address Chapin Building, Medicine Lodge, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Frank Hamlin (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Frank Hamlin

909 1st Nat'l Bank Bldg., Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 14th day of August, 1967.

Amy O. Brossette

Amy O. Brossette

Notary Public.

My commission expires June 10, 1970

DONOVAN "C" #1

Casing Records:

8 5/8" - 189'  
5 1/2" - 4821'

Company: Aylward Drilling Company  
Contractor: Aylward Drilling Company

Commenced: August 6, 1956  
Completed: August 23, 1956

Location: NW SW SE 6-34-12W  
Barber County  
Kansas

Elev.: 1528 RB - 1526 DF

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Red Rock	0	189	Set 8 5/8" Surf. Pipe @ 189' w/175 sx.
Red Bed	189	1055	
Red Rock	1055	1275	
Salt	1275	1385	
Shale and shells	1385	1725	Geological Tops:
Lime	1725	2375	Elgin Sand 3612
Lime and shale	2375	3050	Heebner 3856
Lime	3050	3150	Base/Oread 3922
Broken lime and shale	3150	3270	Lansing 4038
Shale and Lime shelves	3270	3310	Mississippian 4744
Lime	3310	3355	RTD 4821
Lime and shale	3355	3519	
Lime	3519	3522	
Lime and shale	3522	3610	DST 4750-4805, open 40 min. Gas to surf. in 1 1/2 min., gauged 2,800 MCF in 3 min.; Rec. 340' Gsy. SW, ISIP 1725# in 20 min., FP 665-790#, FBHP 1650# in 30 min.
Sand	3610	3810	
Lime and shale	3810	3830	
Lime	3830	4039	
Lime and shale	4039	4087	
Lime	4087	4340	
Lime and shale	4340	4542	
Lime	4542	4572	
Lime and shale	4572	4622	Set 5 1/2" casing @ 4821' w/75 sx cement.
Lime	4622	4647	
Lime and shale, broken	4647	4675	
Lime and shale	4675	4728	Cable Tool Data:
Lime	4728	4734	Perforate 48 holes from 4762-72 (L.W. rec.) (Lane Wells measurements which are 40' higher than Schlumberger)
Sand	4734	4735	5.
Lime and shaley lime	4735	4765	
Chert	4765	4802	
Lime	4802	4821	

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 JUN 28 1967  
 6-28-67  
 CONSERVATION DIVISION  
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Jessor

Subscribed and sworn to before me this 30th day of August, 1956

Duane Jessor  
DUANE JESSOR Notary Public

My commission expires December 11, 1957