

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 6 Twp. 34S Rge. 12 (E) (W)

Location as "NE/CNWxSWx" or footage from lines NW NE NE 212x22

Lease Owner Bulldog Pipe & Supply

Lease Name McCracken Well No. B-1

Office Address 309 Mayo Building Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__

Plugging commenced _____ 4-20 19 69

Plugging completed _____ 4-23 19 69

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4649 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	29 1/2	None
				5 1/2	None	3828

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Blow out gas. Sanded to 4600'. Dumped 5 sacks of cement.
Cleaned out cellar. Working pipe.

Working pipe. Shot pipe at 3810'. Pulling pipe.

Plugging well. Bailed rock bridge at 250'. Dumped 25 sacks of cement. Mudded hole and rock bridge. Capped well with 10 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 29 day of April, 1969

My commission expires May 27, 1969 Notary Public.

ROTARY DRILLING LOG

OPERATOR: Bachus Oil Company
 McCracken "B" #1
 C NW NE Sec. 6-34-12W,
 Barber County, Kansas

CONTRACTOR: Prime Drilling Company
 COMM: 12/17/57
 COMP: 1/1/58

Remarks: Set 8-5/8" surface casing
 at 294' cemented with 225 Sacks
 Pozmix, 2% D.C.

Formations:

Surface Clay & Rock	30'
Red Bed & Shale	243'
Red Bed & Shells	295'
Red Bed & Red Rock	685'
Shale & Shells	1440'
Anhydrite	1495'
Shale & Shells	1600'
Shale & Lime	1710'
Lime & Shale	1790'
Lime Sandy Streaks	1890'
Lime & Shale	2005'
Lime	2060'
Lime & Shale	2390'
Shale & Lime	2440'
Lime & Shale	2735'
Shale & Lime	2725'
Lime & Shale	3660'
Sand & Shale	3705'
Shale & Lime	4055'
Lime	4385'
Lime Cherty	4435'
Lime	4550'
Cherty Lime	4562'
Lime	4605'
Cherty Lime	4630'
Lime	4649'
Rotary Total Depth	4649'

Set 5-1/2" casing at 4647-1/2' cemented
 with 150 sacks common cement.

We certify the above log is true and
 correct to the best of our knowledge
 and belief.

PRIME DRILLING COMPANY

R. R. McNicol

R. R. McNicol