


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barber County. Sec. 1 Twp. 34S Rge. 12 ~~XXX~~ (W)
Location as "NE/CNWxSWx" or footage from lines C N/2 SE/4
Lease Owner Bowers Drilling Company, Inc.
Lease Name Schubach Well No. 1
Office Address 1434 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3-2-68 19
Application for plugging filed 3-6-68 19
Application for plugging approved 3-1-68 19
Plugging commenced 3-2-68 19
Plugging completed 3-2-68 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4786 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	324	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heaby mud to 300'
Set plug at 300 w/25 sacks cement;
Filled hole with mud to 40'
Set plug at 40' w/10 sacks eement

RECEIVED
STATE CORPORATION COMMISSION
MAR 8 - 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Bowers Drilling Company, Inc.
Address 1434 Wichita Plaza, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
1434 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of March, 19 68

My commission expires 6-30-71
Sherry Gish Notary Public.

WELL LOG

COMPANY: Bowers Drilling Company, Inc.
 CONTRACTOR: Bowers Drilling Company, Inc.
 FARM: #1 Schupbach
 LOCATION: C N/2 SE/4 Section 1-34S-12W
 Barber County, Kansas
 COMMENCED: 2-22-68
 COMPLETED: 3-2-68
 ELEVATION: 1537 Kelly Bushing

0 - 1100	Redbed	
1100 - 1260	Shale and shells	Set 8-5/8" casing at 324 w/225 sacks
1260 - 1717	Shale and lime	
1717 - 2327	Lime	
2327 - 3758	Lime and shale	
3758 - 3885	Lime, shale and sand	
3885 - 4060	Lime and shale	
4060 - 4184	Lime	
4184 - 4335	Lime and shale	
4335 - 4547	Lime	
4547 - 4637	Lime and shale	
4637 - 4730	Lime	
4730 - 4786	Lime and shale	
4786	T. D.	

RECEIVED
 STATE CORPORATION COMMISSION
 3-8-68
 MAR 8 - 1968
 CONSERVATION DIVISION
 Wichita, Kansas

SAMPLE TOPS:

Elgin Zone	3597 (-2060)
Heebner	3796 (-3359)
Toronto	3804 (-2267)
Douglas	3824 (-2287)
Lansing	3993 (-2456)
B/Kansas City	4521 (-2984)
Mississippian	4692 (-3157)

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Schupbach located C N/2 SE/4 Section 1-34S-12W, Barber County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers
 Emil E. Bowers, President

Subscribed and sworn to before me, a Notary Public, in and for the State of Kansas this 6th day of March, 1968.

Sherry Gish
 Sherry Gish, Notary Public

My commission expires 6-30-71