


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Barber County. Sec. 32 Twp. 33 Rge. 14 (E) (W) X
Location as "NE/CNW/SW" or footage from lines C NW/4
Lease Owner Specter Pipe & Supply, Inc.
Lease Name Davis Ranch unit no. 2 Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) gas
Date well completed 3-28-59 19__
Application for plugging filed June 28, 1973 19__
Application for plugging approved June 26, 1973 19__
Plugging commenced 7-19-73 19__
Plugging completed 7-26-73 19__
Reason for abandonment of well or producing formation failure to produce profitably
If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well G.R. Biberstein
Producing formation Mississippi Depth to top 4702 Bottom 4779 Total Depth of Well 4780 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8	201	none
				4 1/2" OD	4729ft.	3719 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Made bottom hole plug back with sand to 4700ft. Mixed and ran 3 sacks cement thru dump bailer. Mudded hole to 120 ft. -set 20 ft. rock bridge filled hole with 5 1/2 yards ready-mix concrete to base of cellar

RECEIVED
STATE CORPORATION COMMISSION

AUG 2 1973
8-2-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Company
Address Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) [Signature]
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of August, 19 73

My commission expires May 21, 1975

Notary Public.

15-007-16768-0000


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

Company- CHAMPLIN OIL & REFINING CO.
Farm- Davis Ranch Ut.#2 No. 1

SEC. 32 T. 33 R. 14W
Approx. C NW/4

Total Depth. 4780'
Comm. 3-9-59 Comp. 3-28-59
Shot or Treated.
Contractor. Armer Drig. Co.
Issued. 5-30-59

County Barber
KANSAS


CASING:
3" @ 200'
5" @ 4778.66'

Elevation. 1748' DE
Production. 7,000,000 CFG

Figures Indicate Bottom of Formations.

shale & shells	200
red bed & shells	650
shale & shells	1340
shale & lime	1925
sd. lime & shale	2020
lime	2450
lime & shale	2710
shale	2910
shale & lime	3325
lime	3605
shale & lime	4025
lime	4240
shale & lime, sand	4315
lime & shale	4360
lime	4671
lime & shale	4715
lime	4780 RTD
Total Depth	

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1973
6-26-73
CONSERVATION DIVISION
Wichita, Kansas

TOPS:	SAMPLE	ELECTRIC
Huebner	3925	3931
Toronto	3949 ?	3936 ?
Douglas	3968	3961
Lansing K.C.	4135	4125
Base/K.C.	4606	4607
Marmaton	4616	4620 ?
Cherokee	-	4690
Mississippi	4702	4709

DST #1 - 4706-30/120". GTS/7". Rec.
98' Drig. mud. ISIP 1800#/30"; PSIP
1720#/60"; IFP 80#; FFP 60#.

DST #2 - 4730-4765/120" GTS/3". Rec.
143' Drig. Mud. ISIP 1800#/30"; PSIP
1830#/60"; IFP 620#; FFP 640#.