


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD

Barber County. Sec. 32 Twp. 33 Rge. 14 (E) (W) X  
Location as "NE/CNW/SW" or footage from lines 50' W of C NE/14  
Lease Owner Specter Pipe & Supply, Inc.  
Lease Name Davis Ranch unit no. 1 Well No. 1  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) gas  
Date well completed 4-21-59 19\_\_  
Application for plugging filed June 24, 1973 19\_\_  
Application for plugging approved June 26, 1973 19\_\_  
Plugging commenced 7-24-73 19\_\_  
Plugging completed 7-30-73 19\_\_  
Reason for abandonment of well or producing formation failure to produce profitably  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation Mississippi Depth to top 4647 Bottom 4729ft. Total Depth of Well 4732 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 5/8	199 ft.	none
				8 5/8" OD	849 ft.	631.41
				4 1/2	4729 ft.	3952.27 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Made bottom hole plug back with sand to 4625 ft. Mixed and ran 3 sacks cement thru dump bailer. Mudded hole to 120 ft. -set 20 ft. rock bridge. Filled hole with 5 yards ready-mix concrete to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 10 1973  
8-10-73  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 3 1973  
8-3-73  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling Co  
Address Gt. Bend, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
Specter Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
\_\_\_\_\_  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 19 73

My commission expires May 21, 1975  
Melina M. Lindahl  
Notary Public.

5-007-19093-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas




Company. CHAMPLIN OIL & REFINING CO.  
Farm. Davis Ranch Unit No. 1  
#1

SEC. 32 T. 33 R. 14W  
50' W of C NE/4

Total Depth. 4732'  
Comm. 4-2-59 Comp. 4-21-59  
Shot or Treated.  
Contractor. Armer, Inc.  
Issued. 8-8-59

County Barber  
KANSAS



Elevation. 1707' DF

Production. 16 BOPD &  
7,200,000 CFG

Figures Indicate Bottom of Formations.

CASINO:	
13"	200'
8"	849'
5"	4729'
red bed	70
red bed & rock	200
red bed	703
dry drilling	851
shale, red bed & shells	1240
red bed & shale	1675
shale & lime	2310
lime	2415
lime & shale	2690
shale	3080
shale & lime	3955
lime	4015
lime & shale	4050
lime	4095
lime, chalky, lime & shale	4155
lime & shale	4360
lime	4545
lime & shale	4590
lime	4612
lime & shale	4647
lime	4730 RTD
lime	4732
Total Depth	

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 26 1973  
6-26-73  
CONSERVATION DIVISION  
Wichita, Kansas

TOPS:	SAMPLE	ELECTRIC
Heebner	3882	3880
Toronto	3894	3895
Douglas	3914	3911
Lansing-Kansas City	4074	4075
Base Kansas City	4546	4548
Marmaton	4559	4560
Cherokee	4628	4632
Mississippian	4647	4648