

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15111-20113-0000

LEASE NAME Trust

WELL NUMBER #2

SPOT LOCATION C NW SE NW

SEC. 9 TWP. 16 RGE. 10E (E) or (W)

COUNTY Lyon

Date Well Completed \_\_\_\_\_

Plugging Commenced 3-15-86

Plugging Completed 3-17-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Mack Energy Company

ADDRESS 702 Union Center Bldg Wichita, Kansas 67202

PHONE # (316) 262-2688 OPERATORS LICENSE NO. 8759

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.O. 3484'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	214'	none
				4-1/2"	3307'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

No Pipe Recovery. Ran flag on wireline and found hole @554' & 1176', couldn't get past 2325'. Pumped 325 sacks 60/40 pos down 4-1/2" casing. Had circulation but couldn't get cement to circulate. Let cement set 3 hrs., tagged cement @400'. Dumped 35 sacks cement down 4-1/2" casing & filled up. Hooked onto surface and pumped 45 sacks and annulus pressured up. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 24th day of March, 1986



RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public

My Commission expires: \_\_\_\_\_

MAR 27 1986  
3-27-86  
CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4  
Revised 01-84

15-111-20113-0000



# RADIATION-GUARD LOG

COMPANY MACK OIL COMPANY

WELL TRUST # 2      MACK ENERGY  
702 Union Center  
Wichita, Kansas 67202  
(316) 262-2688

FIELD \_\_\_\_\_

COUNTY LYON      STATE KANSAS

Location C-NW-SE-NW      Other Services:  
NONE

Sec. 9      Twp 16S      Rge 10E

COMPANY MACK OIL COMPANY  
WELL TRUST # 2  
FIELD \_\_\_\_\_  
County LYON      State KANSAS

Permanent Datum GROUND LEVEL      Elev. 1331'      Elev.: K.B. 1336'  
Log Measured From KELLY BUSHING      Ft. Above Perm. Datum      D.F. 1333'  
Drilling Measured From KELLY BUSHING      G.L. 1331'

Date	11-5-72	11-5-72	11-5-72	
Run No.	ONE	GAMMA	NEUTRON	GUARD
Depth-Driller	3483'	3483'	3483'	
Depth-Welex	3484'	3484'	3484'	
Btm. Log Inter.	3476'	3484'	3476'	
Top Log Inter.	0'	0'	214'	
Casing-Driller	@	@	8-5/8" 214'	@
Casing-Welex			8-5/8" 214'	
Bit Size			7-7/8"	
Type Fluid in Hole			WATER BASE	
			CHEMICAL MUD	
Dens.   Visc.			9.4   38	
pH   Fluid Loss	ml	ml	9.0   19.8 ml	ml
Source of Sample			FLO LINE	
R <sub>100</sub> @ Meas. Temp.	@ °F	@ °F	1.02 @ 64 °F	@ °F
R <sub>100</sub> @ Meas. Temp.	@ °F	@ °F	.714 @ 64 °F	@ °F
R <sub>100</sub> @ Meas. Temp.	@ °F	@ °F	1.53 @ 64 °F	@ °F
Source R <sub>100</sub> R <sub>100</sub>			MEAS	
R <sub>100</sub> @ BHT	@ °F	@ °F	.62 @ 104 °F	@ °F
Time Since Circ.			2 HOURS	
Max. Rec. Temp.	°F @	°F @	103°F @ TD	°F @
Equip. & Location	8766 IGT. BEND			
Recorded By	C. PEBLEY			
Witnessed By	MR. LARSH			

RECEIVED  
STATE CORPORATION COMMISSION

FEB 10 1986

CONSERVATION DIVISION  
Wichita, Kansas