

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15711-20107-0000

LEASE NAME Trust

WELL NUMBER #1

SPOT LOCATION NW NE SW

SEC. 9 TWP. 16 SRGE. 10E (E) or (W)

COUNTY Lyon

Date Well Completed _____

Plugging Commenced 3-11-86

Plugging Completed 3-15-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mack Energy Company

ADDRESS 702 Union Center Bldg. Wichita, Kansas 67202

PHONE # (316) 262-2688 OPERATORS LICENSE NO. 8759

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3215'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	201'	none
				5-1/2"	3048'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

No Pipe Recovery. Fluid @ 4', couldn't get down hole. Ran flag and found hole @ 893', hooked onto 5-1/2" casing and pumped in 250 sacks 60/40 pos, 6% gel and 60 sacks common. Circulated cement up 8-5/8" surface pipe from 893'. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso

(employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 24th day of March, 19 86

My Commission expires: _____



STATE CORPORATION COMMISSION
Notary Public

MAR 27 1986
3-27-86
CONSERVATION DIVISION

Schlumberger

DUAL INDUCTION-LATEROLOG
WITH LINEAR CORRELATION LOG

COUNTY LYON FIELD or LOCATION SEC. 9-16S-10E TRUST NO. 1 COMPANY MACK OIL COMPANY	COMPANY	MACK OIL COMPANY	HAL
	WELL	TRUST NO. 1	(318) 262-2688
	FIELD	WILDCAT	702 Union Center Wichita, Kansas 67202
	COUNTY	LYON	STATE KANSAS
	LOCATION	NW-NE-SW	Other Services: FDC-GR
	Sec. 9	Twp. 16S	Rge. 10E

Permanent Datum: GROUND LEVEL	Elev. 1316	Elev.: K.B. 132
Log Measured From KB	5 Ft. Above Perm. Datum	D.F. ---
Drilling Measured From KB		G.L. 131

Date	8/16/72			
Run No.	ONE			
Depth-Driller	3215			
Depth-Logger	3215			
Btm. Log Interval	3209			
Top Log Interval	200			
Casing-Driller	8 5/8 @ 201	@	@	@
Casing-Logger	200			
Bit Size	7 7/8			
Type Fluid in Hole	FG-CS-SA			
Dens.	9.5	42		
pH	Fluid Loss	9	8.8 ml	ml
Source of Sample	CIRCULATED			
R _m @ Meas. Temp.	1.76 @ 90 °F	@	°F	@
R _{mf} @ Meas. Temp.	1.26 @ 90 °F	@	°F	@
R _{mc} @ Meas. Temp.	--- @ --- °F	@	°F	@
Source: R _{mf} R _{mc}	M	---		
R _m @ BHT	1.62 @ 98 °F	@	°F	@
Time Since Circ.	2 HOURS			
Max. Rec. Temp.	93 °F			
Equip. Location	4571 WICHITA	STATE CORPORATION COMMISSION		
Recorded By	MC GINNESS	RECEIVED		
Witnessed By	MC CALEB	FEB 10 1986		

CONSERVATION DIVISION
Wichita, Kansas