

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-05203-00-00
Spot: SESWNW Sec/Twnshp/Rge: 31-20S-7W
2960 feet from S Section Line, 3999 feet from E Section Line
Lease Name: BROTHERS I S Well #: 3-A
County: RICE Total Vertical Depth: 3322 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3309		
SURF	8.625	117		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2013 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: PER KCC RULES AND REGULATIONS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/30/2013 4:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OPEN HOLE TO 3260' AND CAP WITH 4 SX'S CEMENT. PERFORATE AT 1050', 600', AND 250'. RUN TUBING TO 1050' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CC. LET SET AWHILE, ATTEMPTED TO TAG COULD NOT. RUN TUBING BACK TO 1050' AND PUMPED 35 MORE SX'S COMMON WITH 3% CC. LET SET OVER 1 HR.--TAGGED AT 715'. RUN TUBING TO 600' AND PUMP 35 SX'S COMMON WITH 3% CC, PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. RUN 1" DOWN BACKSIDE OF 4.5" AND PUMPED 120 SX'S TO TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3309	3323	OH	

Remarks: LOG TECH OF KS TICKET #7768. COPELAND TICKET #40641.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
02/12/14 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

JAN 29 2014

RECEIVED

JK