

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20594-00-00
Spot: NWNWSENW Sec/Twnshp/Rge: 12-34S-34W
3942 feet from S Section Line, 3917 feet from E Section Line
Lease Name: ENGEL JACK UNIT Well #: 1-12
County: SEWARD Total Vertical Depth: 6600 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6000		WITH 10 SX CMT
DVT		3092		
PROD	4.5	6599	1670	WITH 300 SX CMT
SURF	8.625	1621		WITH 700 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/07/2014 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Set CIBP @ +/- 6000'. Circ wellbore w/ 9.5 ppg, 36 vis mud & cap CIBP w/ +/- 10 sx Class C cement. Pump 20 sx cement plug @ 3142' - 3042' to cover DV tool @ 3092'. Cut csg at freepoint (if freepoint is found to occur above 1600'), keeping hole full of mud at all times. Notify KCC of anticipated depth of cement plugs in order to cover known anhydrite formation. Pump 80 sx cement from 1721' - 1421' to cover surface casing shoe. Tag plug & top off w/ additional cement, if needed. Pump 60 sx cement from 550' - 325' to cover known anhydrite formation. Mix and pump 20 sx cement from 64' - 4' below ground level. Weld on ID plate. Restore location to landowners specifications.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 01/07/2014 5:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 6000' WITH 10 SX CMT. PUMP 20 SX CMT AT 3142' TO COVER DV TOOL. 1ST PLUG AT 1721' WITH 80 SX CMT. 2ND PLUG AT 550' WITH 60 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6046	6076		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

RECEIVED
JAN - 9 2014
KCC DODGE CITY

Signed

[Signature]
01/16/14 (TECHNICIAN)

KCC WICHITA

JAN 16 2014

RECEIVED

Form CP-2/3