

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20921-00-00
Spot: E2W2SWSE Sec/Twnshp/Rge: 4-26S-24W
660 feet from S Section Line, 2115 feet from E Section Line
Lease Name: LIX Well #: 3-4
County: FORD Total Vertical Depth: 4948 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	314		WITH 200 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 01/13/2014 2:00 AM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Revd. from: MIKE GODFREY Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1680' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 80 SX CMT. 3RD PLUG AT 350' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 01/13/2014 4:00 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

1ST PLUG AT 1680' WITH 50 SX CMT. 2ND PLUG AT 900' WITH 80 SX CMT. 3RD PLUG AT 350' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

Signed Richard M. Lacey
01/13/14 (TECHNICIAN)

RECEIVED

JAN 14 2014

KCC DODGE CITY

KCC WICHITA Form CP-2/3

JAN 16 2014

RECEIVED