

5 020279

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 111-20107-0000

NWNE 1/4 SEC. 9, T. 16 S, R. 10 W(E)
2310 feet from N(S) section line
3630 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8759

Lease Name Trust Well # 1

Operator: Mack Energy Co.

County Lyon 104.49

Name & Address 702 Union Center Bldg.

Well Total Depth 3215 feet

Wichita, Kansas 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 3/4 feet 201

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 8:00 AM Day: 15 Month: March Year: 19 86

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316.938.2457

were: Circulate cement through hole in 5 1/2" casing @ 887. Circulate to cellar, close in and pump total of 250 sacks 60/40 mix w/ 6% gel

RECEIVED
STATE CORPORATION COMMISSION

3-24-86
MAR 24 1986

Plugging Proposal Received by Ralph Tittel
CONSERVATION DIVISION
Wichita, Kansas
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:10 AM Day: 15 Month: March Year: 19 86

ACTUAL PLUGGING REPORT Cement circulated down 8 3/8" and through hole in 5 1/2" casing back up through 8 3/8" casing to cellar. 8 3/8" closed in and balance of 250 sacks pumped down 5 1/2" casing. Cement fell approx. 200'. 5 1/2" filled to base of cellar with approx. 100 sacks 60/40 Puz. 3/17/86. witnessed by Ralph Tittel
5 1/2" - 3048' - 125 SKS P.C.F. 2962

Remarks: No casing recovered Sun Cementing Co. Ticket # 1351
(If additional description is necessary, use BACK of this form.)

INVOICED

MAR 25 1986

Signed Ralph Tittel
(TECHNICIAN)

DATE _____
INV. NO. 13073

3-15

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM C
Rev. 6/4

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-111-201070000 (of this well) 6/86
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Mack Energy Co. OPERATORS LICENSE NO. 8759

ADDRESS 702 Union Center Bldg. Wichita, Ks. 67202 PHONE # (316) 262-2688

LEASE (FARM) Trust #1 WELL NO. _____ WELL LOCATION NW NE SW COUNTY Lyon

SEC. 9 TWP. 16s RGE. 10e (E) or (S) TOTAL DEPTH 3215' PLUG BACK TO 3018'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 201' CEMENTED WITH 150 SACKS

CASING SIZE 5 1/2" SET AT 3048' CEMENTED WITH 125 SACKS

PERFORATED AT 2962-68'

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL _____

Will plug according to rules & regulations of State of Kansas.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS AOC-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Immediately

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH R.S.A. 55-101 et seq AND THE RULES & REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

O.D. Mellott PHONE # (316) 793-8721

ADDRESS Rt 3, Great Bend, Ks. 67530

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050

ADDRESS Box 347, Chase, Ks. 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]

(Operator or Agent)

RECEIVED
CORPORATION COMMISSION

DATE:

February 7, 1986

FEB 10 1986