

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-00276-00-00
Spot: NW Sec/Twnshp/Rge: 13-32S-38W
1402 feet from N Section Line, 1372 feet from W Section Line
Lease Name: WEBBER Well #: 1
County: STEVENS Total Vertical Depth: 2798 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	8.625	2494	0	WITH 150 SX CMT
SURF	13	602		WITH 75 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/24/2014 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2410' WITH 10 SX CMT. PERFORATE @ 1750'. RUN PACKER TO 1100' & PUMP 80 SX CMT. TOG TOC. PERFORATE @ 632' & SPOT 100 SX CMT. PERFORATE @ 300' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 01/27/2014 10:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TOP OF FISH @ 2348'. CIRCULATE HOLE WITH 100 BBL MUD & SPOT 75 SX CMT UP TO 2160'. 1ST PLUG PERFORATE @ 1750' & SPOT 80 SX CMT. SET PACKER AT 1100'. LOAD TBG & PRESSURE CMT TO SQUEEZE 10 BBLS INTO PERFORATIONS. 2ND PLUG PERFORATE @ 632'. SET PACKER @ 300' & PUMP 100 SX CMT. 3RD PLUG PERFORATE @ 300' & PUMP 220 SX CMT. TOP OFF WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2542	2766		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

RECEIVED
JAN 31 2014
KCC DODGE CITY

KCC WICHITA

Form CP-2/3

FEB 12 2014

RECEIVED

