

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22159-00-00
Spot: E2SESWSW Sec/Twnshp/Rge: 2-7S-20W
330 feet from S Section Line, 1000 feet from W Section Line
Lease Name: T D GOTTSCHALK Well #: 4-2
County: ROOKS Total Vertical Depth: 3646 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 400 N WOODLAWN ST, STE 18
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3590		
PROD	4.5	3646		575 SX
SURF	8.625	294		180 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2013 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE FRITZLER Company: FRITZLER TRUCKING INC. Phone: (785) 798-5101

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Production perforations: 3511' - 3529'

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2013 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3500' and pumped 75 sx cement w/225 # hulls. Pulled tubing to 2300' and pumped 75 sx cement w/150 # hulls. Pulled tubing to 1100' and pumped 80 sx cement w/150 # hulls to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing w/40 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 10 sx cement. Maximum pressure 300 psi.

GPS: 39.46732N -099.52476

Perfs:

Top	Bot	Thru	Comments
3598	3602		
3524	3529		
3511	3515		

Remarks: SWIFT TICKET # 25321

Plugged through: TBG

District: 04

Signed

Pat Bedore
12/12/14

Pat Bedore

(TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

JAN 09 2013

JAN 22 2014

RECEIVED