

To: 1 041225
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 007-22,515 -~~0000~~
NW SE SW, SEC. 30, T 33 S, R 14 W/E
990 feet from S section line
3630 feet from E section line

12-19
TECHNICIAN'S PLUGGING REPORT
Operator License # 5010
Operator: Knighton Oil Company, Inc.
Name: 221 S. Broadway, Ste. 710
Address: Wichita, KS 67202

Lease Name Davis Well # 8
County Barber 162.24
Well Total Depth 4992 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 207

Abandoned Oil Well Gas Well Input Well SWD Well D&A *ANB 200*
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address 107 W. Fowler, P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11 a.m. Day: 19 Month: 12 Year: 19 96
Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

Work: 4 1/2" at 4990' w/200 sx cement, PBSD 4990', Perfs at 4889-94'
1st plug sand back to 4835' and dump 4 sx cement on top of sand through bailer.
2nd plug pump 300 lbs. hulls, 10 sx gel, 75 sx cement, 10 sx gel, 100 lbs. hulls, release
10 3/4" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Bill Johnson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 19 Month: 12 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4660' and dumped 4 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 200 lbs. hulls, and 125 sx cement.
Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3600' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (did not) (did) observe this plugging.

INVOICED
DATE 1-2-97
INV. NO. 47301

Signed *Stephen J. Puffer* (TECHNICIAN)