

1 080561

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-01052-0000

C SW/4 SEC. 32, T 33 S, R 14 WAE

1320 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Lease Name Davis Ranch Well # D-2

Operator: Champlin Petroleum Company  
Name &  
Address 6441 N. Grand Blvd.

County Barber

Oklahoma City, OK 73112

Well Total Depth 4799 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 13 3/8 feet 199

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B.J. Titan Services License Number \_\_\_\_\_

Address 2601 NW Expwy, Suite 710W, Oklahoma City, OK 73112

Company to plug at: Hour: 9 a.m. Day: 27 Month: 10 Year: 19 86

Plugging proposal received from Virgil Campbell

(company name) Champlin Petroleum (phone) 405-242-2001

were: 4 1/2" at 4798 PRTD 4768' Perfs at 4740-61' Elevation 1677' GL

1st plug set CIBP at 4660'

2nd plug pump 1 sx hulls and 150 sx cement down 4 1/2" annulus, 200 sx cement down 13 3/8" annulus.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11 a.m. Day: 28 Month: 10 Year: 19 86  
10-27-86

ACTUAL PLUGGING REPORT 1st plug squeezed well down 4 1/2" with 2 sx hulls and 200 sx cement - well on vacuum.

2nd plug pumped down 8 5/8" X 4 1/2" annulus with 100 sx cement.

Maximum pressure 150 psi and shut in 50 psi.

3rd plug pumped 100 sx cement with 2 sx hulls.. 4 1/2" on vacuum.

10-28-86 Tagged cement in 4 1/2" at 752', filled 4 1/2" with 48 sx cement. Completed at 11 a.m.

10-30-86 Cut 13 3/8" off, cement, was tagged at 150', filled backside with cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.  
(If additional description is necessary, use BACK of this form.)

(Plugging Technician) observe this plugging.

Signed J. H. [Signature]  
(TECHNICIAN)

DATE 11-4-86

INV. NO. 15292  
10-28