


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barber County, Sec. 27 Twp. 33 Rge. 14W (E) (W)
Location as "NE/CNW/SE" or footage from lines C W/2 NW
Lease Owner Bulldog Pipe & Supply Company Attn: Robert Greenberg
Lease Name U. B. Harbaugh "A" Well No. 1
Office Address 604 Mayo Bldg., Tulsa, OK 74103
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed _____ 19____
Application for plugging filed 8-09-71 19____
Application for plugging approved 8-09-71 19____
Plugging commenced _____ 19____
Plugging completed 8-24-71 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4708 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1203 ft 8 5/8 surface pipe cemented with 450 sacks. 4706 ft 4 1/2 long string cemented with 100 sacks. Top perf. 4708 ft. Sand back to 4665 ft. 3 sacks cement with bailer. Pulled 2500 ft 4 1/2. Set 20 ft rock bridge at 320 ft. Fill hole with 5 yds redimix to surface.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Clarke Oilfield Service
Address _____

STATE OF _____ COUNTY OF _____ ss. _____ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

(Address) _____

Subscribed and Sworn to before me this _____ day of _____, 19____

My commission expires _____

Notary Public.

DRILLING LOG

Company: Bachus Oil Company
721 East Central
Wichita, Kansas

Lease: U. B. Harbaugh

Well: "A" #1

Location: Center W/2 NW/4 of Section 27-33S-14W
Barber County, Kansas

Date Comm: 7-22-58

Date Comp: 8-6-58

T. D. : 4708 1/2'

Casing: 8 5/8" to 1202.84' W/450 sacks reg. cement
5 sacks CC 6 sacks Gel.
4 1/2" to 4707 1/2' W/100 sacks common cement

Figures Indicate the Bottom of Formation

0-165	Red Bed, Gyp & Shells
670	Red Rock & Shells
760	Shale & Lime Stks
1180	Shale & Shells
1209	Shale & Lime
1700	Shale
1860	Lime & Shale
2605	Lime
2985	Lime & Shale
3245	Shale & Lime
3353	Lime & Shale
3515	Sandy Lime & Shale
3749	Shale & Lime
4045	Lime & Shale
4518	Lime
4546	Lime & Shale
4578	Lime & Shale
4653	Lime
4673	Miss.
4708	Lime

I certify the above to be true and correct to the best of my knowledge and belief.

BACHUS OIL COMPANY

BY W. A. Cecil
WM. A. CECIL

Subscribed and sworn before me this 12th day of August, 1958.

Gail L. Thyfault
Gail L. Thyfault
Notary Public

My Commission Expires:

10-19-60