


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber County, Sec. 37 Twp. 33S Rge. 14W (E) (W)
Location as "NE/CNW/SE/SW" or footage from lines. NW SW
Lease Owner Braden Deem, Inc.
Lease Name Wheat #2 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2/19/73 19____
Plugging completed 2/22/73 19____
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bihanstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4779 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				<u>8 5/8</u> <u>5 1/2"</u>	<u>278</u> <u>4779</u>	<u>none</u> <u>3529</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, ran sand and set 5 sacks cement. Shot pipe at 3568', 3535', pulled 106 joints. Set rock bridge at 360' and ran 6 yards ready mix. Talled pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
FEB 27 1973
2-27-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor VOTH CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, SS.
WALTER VOTH (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
CHASE, KANSAS (Address)

Subscribed and Sworn to before me this 23rd day of February, 19 73

My commission expires _____
MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

DRILLER'S LOG

WACONIA PETROLIUM CONTACT - No. 1, Sheet 82

Commenced Drilling: 9-2-58
 Completed Drilling: 12-1-58

LOCATION: 0 1/4 SW Section 27-33S-14W,
 Barber County, Kansas

TOTAL DEPTH: 4700'

FORMATION	TOP	BOTTOM
Surface	0	215
Red Bed & Shale	215	924
Shale, Linc & Anhydrite	924	1035
Linc & Shale	1035	1248
Linc	1248	2283
Linc & Shale	2280	2705
Shale	2705	3295
Shale & Linc	3295	3405
Shale & Sand	3405	3505
Shale	3505	3510
Shale, Linc & Shale	3510	3771
Shale & Linc	3771	4134
Linc	4134	4411
Linc & Shale	4411	4470
Linc	4470	4523
Linc & Shale	4523	4583
Linc	4583	4700
T. S.	4700	

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 12 1959
 1-12-59
 CONSERVATION DIVISION
 Wichita, Kansas

COPY