


15-007-19089-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber County, Sec. 28 Twp. 33 Rge. 14 (E) (W) est

Location as "NE/CNW/SW" or footage from lines SE-NW-NE

Lease Owner H. C. Bennett

Lease Name Harbaugh Well No. 1

Office Address

Character of Well (completed as Oil, Gas or Dry Hole) Gas Oil Well

Date well completed 19

Application for plugging filed 3-31-71 19

Application for plugging approved 4-2-71 19

Plugging commenced 4-8-71 19

Plugging completed 4-10-71 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Barbstine

Producing formation Depth to top Bottom Total Depth of Well 4636 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	392'	None
				5 1/2"	4714'	3850.04

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled bottom from 4686' to 4600' with gravel. Mixed and dumped 5 sacks of cement.

Set a 20' rock bridge from 320' to 300'. Dumped 5 yards of ready mix cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Flint Eng. & Const. Co.

Address 2375 W. Central, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Richard C. Hausman

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of April, 1971

Jeanne J. Davis

Notary Public.



September 19, 1971

15-007-19089-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

Company: SUN OIL COMPANY
Farm: Harbaugh

No. 1

SEC. 28 T. 33
SE NW NE

R:LLW

Total Depth. 4715'

Comm. 7-1-58

Comp. 7-18-58


Shot or Treated.

Contractor. Capitt Drlg., Inc.

Issued. 11-29-58

County Barber

KANSAS



Elevation. 1670 DE

Production. 10,000,000 CFG
CAL OPEN FLO

CASINO:

13 3/8" 80' w/ 75 sx. cem.
8 5/8" 392.42' w/375 sx. cem.
5 1/2" 4714' w/150 sx. cem.
2" ROE at 4607'

Figures Indicate Bottom of Formations.

SHALE AND SAND	80
shale and sandy shale	690
sand	770
shaly sand and lime	1335
lime w/streaks shale	2075
shaly lime	2350
lime w/streaks shale	3015
limey shale	3110
lime	3525
shale	3537
shaly lime	3615
shale	3645
lime	3690
limey shale	3835
lime	3905
lime and shale streaks	4073
lime (Lansing)	4539
lime (Marmaton)	4618
lime (Mississippi)	4680
Total Depth	

(Gas) (4626-4666')

TOPS: SCOUT	
Lansing	4073
Mississippi Dolomite	4618

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1971
CONSERVATION DIVISION
Wichita, Kansas