

15-007-01142-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER MAY 6, 1958

LEASE NAME DAVIS RANCH A

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 28 TWP. 33 RGE. 14 (NW) (W)

COUNTY BARBER

Date Well Completed

Plugging Commenced 4-14-1992

Plugging Completed 4-21-1992

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR BRISTOL RESOURCES CORP.

ADDRESS 6655 So. Lewis #200- Tulsa, Ok. 74136

PHONE#(918) 492-7900 OPERATORS LICENSE NO. 03048

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-17-1992 (date)

by STEVE DURANT (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation MISSISSIPPIAN Depth to Top

PBTD: 4639 T.D. 4640

Show depth and thickness of all water, oil and gas formations.

PERFS: 4586-4626

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	800	8 5/8	800 FT.	0
		0	4639	4 1/2	4639	2517 FT. - 77 JTS.
				2 3/8		2995 FT. - 95 JTS.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

RIGGED UP - HAD TO CUT TBA. AT 2995 FT. - CUT AND PULLED CSG. AT 2517 FT.
4-21-92: ALLIED PUMPED 50SX AT 830' - 40SX AT 400' - 15SX. AT 45'.
60-40 P02. 6% GEL. USED 20SX GEL FOR GEL WATER. RIGGED DOWN
AND MOVED OFF. LOGTECH SET CTRP AND DUMPED 2SX CEMENT ON 4-17-92.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor PRATT WELL SERVICE, INC. License No. 5893

Address P.O. Box 847 Pratt, KS 67124

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BRISTOL RESOURCES CORP.

STATE OF KANSAS COUNTY OF PRATT, ss.


JUDY BERRY

PLUGGING CONTRACTOR

(Employee of) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) 90 PWS, Inc.



SUBSCRIBED AND SWORN TO before me this 24th day of April, 1992

Dorothy M. Ferguson
Notary Public

My Commission Expires February 6, 1993

Oil Well Rod & Tubing Service • Single & Double Drum Units • Truck Mounted Spudders • Power Tubing Tongs • Tubing Crews, Etc.

Experienced Crews
Heavy Pole Masts
Telescoping Derricks
Properly Insured



In Business Since 1946

Carl R. Gates, President
Alma Gates, Sec.-Treas.
723 South Ninnescah
Pratt, Kansas 67124

