

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-01,042 2081

LEASE NAME McGrath A

WELL NUMBER 1

3355' Ft. from S Section Line

3355' Ft. from E Section Line

SEC 16 TWP 33S RGE 14(E or W)

COUNTY Barber

Date Well Completed 8/30/94

Plugging Commenced 2/8/96

Plugging Completed 2/13/96

LEASE OPERATOR OXY USA Inc.

ADDRESS 400 South Main Pratt, KS 67124

PHONE # (316) 672-5630 OPERATORS LICENSE NO. 5447

Character of Well D & A GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/7/96 (date)

by Steve Pfeifer (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Deer Creek Depth to Top 3460' Bottom 3475' T.D. 5010'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian	Gas	4650'	4660'	8.825"	812'	0'
Deer Creek	Oil & Wtr.	3460'	3475'	5.5"	5002'	2913'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Set CIBP at 4580' and dumped 2 sxs cement. Sanded hole back to 3400' and dumped 5 sxs cement. Recovered 2913' of 5-1/2" pipe. Spotted 50 sx plug (60/40 Poz + 6% gell) thru tbg from 827' to 597'. Spotted 50 sx plug (60/40 poz + 6% gell) thru tbg from 410' to 180'. Pulled tbg to 60' and filled hole to surface with 60/40 poz + 6% gell. Well plugged at 11:00 AM 2/13/96. Halliburton Cement Ticket # 907004-X.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address 107 West Fowler Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF KANSAS COUNTY OF Sedgwick, ss.

Lance Fellhoelter (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STEPHEN E. DARWIN  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 3/9/99

(Signature) Lance Fellhoelter  
(Address) 400 S. Main Pratt, KS 67124

SUBSCRIBED AND SWORN TO before me this 29 day of Feb., 1996

Stephen E. Darwin  
Notary Public

My Commission Expires: 3/9/99