

15-007-30194-0000

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 20 Twp. 33S Rge. 14 (W)

Location as "NE/CNW%SW%" or footage from lines C NW NE

Lease Owner James E. Ely

Lease Name Ely Well No. 1

Office Address c/o Sterling Drilling Company, Sterling, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 11, 1965

Application for plugging filed February 13, 1965

Application for plugging approved February 13, 1965


Plugging commenced February 11, 9:30 a.m. 1965

Plugging completed February 11, 11:45 a.m. 1965

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plot

Name of Conservation Agent who supervised plugging of this well A. Elving, Box 248, Pratt, Kansas

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 1874 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	945'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Heavy mud up to 275'. Howco plug and hulls with 25 sacks cement.  
Top plug at 40', Howco plug and hulls with 10 sacks cement, 2 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 23 1965  
2-23-65  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company

Address Box 127, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner, Secretary  
Box 127, Sterling, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of February, 1965

My Commission Expires Jan. 22, 1966  
BERNARD LAUDERMILK

Bernard Laudermilk  
Bernard Laudermilk, Notary Public.

My commission expires \_\_\_\_\_

STERLING DRILLING COMPANY  
Sterling, Kansas

WELL LOG -----Ely #1  
LOCATED: C NW NE Section 20-33S-14W, Barber County, Kansas

OWNER: James E. Ely  
ROTARY DRILLING CONTRACTOR: Group Exploration Company

COMMENCED: January 27, 1965  
COMPLETED: February 14, 1965

ROTARY TOTAL DEPTH: 4874'

LOG

0 - 190	Red Rock
190 - 1100	Shale & Lime
1100 - 1125	Sand
1125 - 1710	Shale
1710 - 2055	Shale & Lime
2055 - 2440	Lime
2440 - 2443	Lime & Shale
2443 - 2595	Lime
2595 - 2970	Lime & Shale
2970 - 3190	Lime, Shale & Chalk
3190 - 3665	Lime & Shale
3665 - 3690	Lime
3690 - 3705	Shale
3705 - 3882	Shale & Lime
3882 - 3920	Shale
3920 - 4033	Lime & Shale
4033 - 4170	Sandy Shale & Sand
4170 - 4210	Kansas City Lime
4210 - 4310	Lime
4310 - 4390	Kansas City Lime
4390 - 4557	Lime
4557 - 4820	Shale & Lime
4820 - 4829	Lime & Chat
4829 - 4874	Mississippian T.D.

CASING RECORD

Ran 31 joints of 8-5/8" new seamless casing, 935' of pipe set at 945' K.B. Cemented with 650 sacks cement, 50 sacks 50 x 50 Pozmix and 600 sacks 2% c.c.

Dry and Abandoned