


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County, Sec. 21 Twp. 33S Rge. 14 (W)

Location as "NE/CNW&SWK" or footage from lines Ctr. SW - SE
Lease Owner Champlin Petroleum Company
Lease Name Davis Ranch "C" Well No. 1
Office Address P. O. Box 308, Ellinwood, Kansas, 67526
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed September 23, 1958
Application for plugging filed April 12, 1965
Application for plugging approved April 13, 1965
Plugging commenced April 23, 1965
Plugging completed April 25, 1965
Reason for abandonment of well or producing formation Non productive

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production November 19 1964
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4675 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8" OD	200'	None
				5 1/2" OD	4673'	588'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with sand from Total Depth to 4600'. Mixed and dumped 5 sacks of cement filling hole to 4560'. Mudded hole from 4560' to 225' and set 10' rock bridge to 215'. Mixed and dumped 35 sacks of cement filling hole to 180' and mudded hole to 35' and set 10' rock bridge to 25'. Mixed and dumped 20 sacks of cement filling hole to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

MAY 3 1965
5365

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ace Pipe Pulling Co.
Address P. O. Box 304, Great Bend, Kansas, 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
J. W. Meyers (employee of owner) or ~~XXXXXX~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Meyers
P. O. Box 308, Ellinwood, Kansas, 67526
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of April, 1965

My commission expires 5-22-66. M. Kenneth Stearns Notary Public.

CHAMPLIN PETROLEUM COMPANY

Davis Ranch "C" #1

Located in the Ctr. SW - SE
of Section 21 - 33S - 14W,
Barber County, Kansas

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1965
4-13-65
CONSERVATION DIVISION
Wichita, Kansas

Drillers Formation Log

0 ^{ft} - 200 ^{ft}	Surface Sand and Shale
200 ^{ft} - 435 ^{ft}	Redbed
435 ^{ft} - 1,000 ^{ft}	Redbed, Shale and Shells
1,000 ^{ft} - 1,410 ^{ft}	Sand, Shale and Shells
1,410 ^{ft} - 1,760 ^{ft}	Shale, Shells and Gyp
1,760 ^{ft} - 1,865 ^{ft}	Shale and Lime
1,865 ^{ft} - 2,000 ^{ft}	Lime and Shale
2,000 ^{ft} - 2,205 ^{ft}	Lime
2,205 ^{ft} - 2,305 ^{ft}	Shale and Lime
2,305 ^{ft} - 2,785 ^{ft}	Lime and Shale
2,785 ^{ft} - 2,930 ^{ft}	Shale and Shells
2,930 ^{ft} - 4,010 ^{ft}	Lime and Shale
4,010 ^{ft} - 4,048 ^{ft}	Sand and Shale
4,048 ^{ft} - 4,375 ^{ft}	Lime
4,375 ^{ft} - 4,413 ^{ft}	Lime and Shale
4,413 ^{ft} - 4,483 ^{ft}	Lime
4,483 ^{ft} - 4,556 ^{ft}	Lime and Shale
4,556 ^{ft} - 4,585 ^{ft}	Lime
4,585 ^{ft} - 4,675 ^{ft}	Lime and Chert
4,675 ^{ft}	TOTAL DEPTH