

15-007-10341-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD


Barber County, Sec. 24 Twp. 33 Rge. 14 (E) (W)

Location as "NE/CNWxSWx" or footage from lines NW SE NE
Lease Owner Messman-Rinehart Oil Co.

Lease Name Lenkner Well No. #2
Office Address 518 Petroleum Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 2-9-62 19
Plugging completed 2-14-62 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Depth to top Bottom Total Depth of Well 4750' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug back with sand to 4640'. Mixed and ran 5 sacks cement thru dump baler. Mudded hole to 230', sat 10' rock bridge. Mixed and ran 20 sacks cement thru dump baler. Mudded hole to 40' and sat 10' rock bridge. Mixed and dump 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
FEB 1 1962
2-16-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15 day of February, 19 62

My commission expires 24 October 1964
Sidney J. Miller Notary Public.

NO. 2 LENKNERWELL LOG

Location: NW SE NE, 24-33S-11W
Barber County, Kansas

Commenced: November 17, 1955

Operator: Gramhart-Miller Oil Company
1005 East Second, Wichita, Kansas

Completed: December 1, 1955

Contractor: Graham-Messman-Rinehart Drilling Co.
1005 East Second, Wichita, Kansas

Elevation: 1834 KB (1828 GL)

Casing Records: 8 5/8" @ 280' w/180 sacks cement
5 1/2" @ 4750' w/100 sacks cement

Productions:

.....L O G.....

Sand-Red Bed	281
Sand-Shale-Gyp	1091
Shale	1920
Shale-Lime	2505
Lime-Shale	2585
Shale-Lime	3225
Shale	3300
Lime-Shale	3568
Shale-Lime	3682
Lime	3775
Shale-Lime	3906
Lime-Shale	3952
Lime	4048
Shale-Lime	4148
Lime	4655
Shale-Lime	4675
Lime	4750 R.T.D.

Sample Tops:

Lecompton 3751 (-1917)
Elgin 3788 (-1954)
Heebner 3969 (-2135)
Toronto 3986 (-2152)
Douglas 4009 (-2175)
Lansing 4147 (-2313)
Marmaton 4623 (-2789)
Mississippi 4697 (-2863)

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART DRILLING COMPANY

By: J. A. Gilliland

J. A. Gilliland

Subscribed and sworn to before me
this 6th day of December 1955.

James H. Lewis
Notary Public

My Commission Expires: November 5, 1958

RECEIVED
STATE CORPORATION COMMISSION

MAR 19 1962
3-19-62
CONSERVATION DIVISION
Wichita, Kansas

NO. 2 LENKNER

Location: NW SE NE, 24-33S-14W
Barber County, Kansas

SUMMARY REPORT: CABLE TOOL ACTIVITY

- 12-8-55 DOC to 4711'. Ran Lane-Wells Log.
Perf 4656-62/23^B. Gas to surface in 1". Ran
Bailer in 30". Had 400' oil in hole.
- 12-9-55 Hole filled 3200' w/oil overnight. Swabbed down.
Swb tests: 1st hr 1 BO; 2nd hr 2 $\frac{1}{2}$ BO. Next 6 hrs
approximately same.
- 12-10-55 Swabbing 2 $\frac{1}{2}$ BO, no wtr, 2% mud. Acidized w/250
gals mud acid and 1000 gals retarded acid. Time-
1 hr. Finished @ 600#. Pressure dropped to 175#
in 10". Swabbed total of 38 BO in 8 hrs.
- 12-11-55 Ran tubing and rods. Completed on 12-11-55 for
 $\frac{1}{4}$ BOPH.

RECEIVED
STATE CORPORATION COMMISSION
MAR. 19 1962
3-19-62
CONSERVATION DIVISION
Wichita, Kansas