

15-007-16651-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Barber County, Sec. 33 Twp. 33 Rge. 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines. NW SE
Lease Owner: Braden-Deem, Inc.
Lease Name: Wheat #4 Well No. _____
Office Address: Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/13/72 _____ 19____
Plugging completed 9/18/72 _____ 19____
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4830 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|---------------|-------------|---------------|
| | | | | 8-5/8 5/2" | 364 4746 | none 3767' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4710', ran sand to 4600' and dumped 5 sacks of cement. Shot pipe at 3772', pulled 116 joints. Bailed fluid to 350' and set 10' rock bridge and dumped 6 yards of ready mix.

PLUGGING COMPLETE.


RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1972
9-22-72
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: KNIGHT CASING PULLING CO., INC.
Address: CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of September, 19 72



Margaret Melcher
Notary Public.

15-007-116651-0000

DRILLERS' LOG

Well Owner: Magnolia Petroleum Company
 Farm Name: Wm. A. Wheat Well No. 4
 Commenced: 6/5/59
 Completed: 6/22/59
 Total Depth: 4830'
 Casing: 8 5/8" @ 364' cemented
 5 1/2" @ 4746' cemented

NW SE
 Sec. 33-33S-14W
 Barber County, Kansas

Elevation:

Contractor: Peel Brothers, Inc.

Production:

Figures below indicate bottoms of formations:

| | | |
|----------------------|-----|------|
| Surface soil | 0 - | 40 |
| Shale & sand streaks | | 200 |
| Red bed | | 745 |
| Shale & shells | | 1785 |
| Shale & lime | | 2120 |
| Lime | | 2210 |
| Lime & shale | | 3270 |
| Lime | | 3340 |
| Shale & lime | | 3940 |
| Lime | | 4590 |
| Lime & shale | | 4635 |
| Lime | | 4814 |
| Lime & shale | | 4830 |
| Total Depth | | 4830 |

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 31 1972
 8-31-72
 CONSERVATION DIVISION
 Wichita, Kansas

This is to certify that the above information is to the best of our knowledge, true and correct

PEEL BROTHERS, INC.

BY: *James M. Throckmorton*

SUBSCRIBED AND SWORN to before me this 24th day of June, 1959

My commission expires: April 27, 1960

Rich East
 Notary Public