

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-22,216-0000

LEASE NAME Hendrix "B"

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2

2970 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 36 TWP. 33 RGE. 14 (X or W)

COUNTY Barber

Date Well Completed 1-11-89

Plugging Commenced 1-11-89

Plugging Completed 1-11-89

LEASE OPERATOR TXO Production Corp.

ADDRESS 1660 Lincoln St. Suite 1800 Denver, CO 80264

PHONE# (303) 861-4246 OPERATORS LICENSE NO. 5171

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-10-89 (date)

by Mr. Lacy (KCC District Agent's Name).

to be filed by  
Is ACO-1 filed? operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 5000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pull

RECEIVED  
STATE CORPORATION COMMISSION  
1-20-89  
JAN 20 1989

Describe in detail the manner in which the well was plugged, indicating where the fluid was placed and the method or methods used in introducing it into the hole. If other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Bottom Plug: @ 800' w/50 sacks cement thru drill pipe

Next Plug: @ 480' w/50

Top Plug: @ 40' w/10

15 sacks in Rat Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Co. License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TXO Production Corp.

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (Employee of Operator) or XXXXXXXXX of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 16 day of January, 19 89

Dorothy M. Hague  
Notary Public

My Commission Expires: 5-5-90

DRILLER'S WELL LOG

DATE COMMENCED: January 3, 1989  
 DATE COMPLETED: January 11, 1989

TKO Production Corp.  
 HENDRIX "B" #2  
 5/2 S/2 NE  
 Sec. 26, T33S, R13W  
 Barber County, Ks.

ELEVATION: 1776 K.B.

0	-	70'	Surface soil, Sand, Clay
70	-	200'	Shale
200	-	2350'	Shale & Lime
2350	-	2956'	Lime & Shale
2956	-	3233'	Lime
3233	-	3675'	Shale & Lime
3675	-	4135'	Lime
4135	-	4288'	Shale & Lime
4288	-	4555'	Lime
4555	-	4603'	Shale & Lime
4603	-	4750'	Lime
4750	-	4839'	Chert & Lime
4839	-	5000'	Lime
		5000'	RTD

Surface Pipe: Set new  
 8-5/8" 20' pipe 0447'  
 w/150 sacks Lite 7-75  
 sacks common 28 gal,  
 38 cc.

A F F I D A V I T

STATE OF KANSAS  
 COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and  
 statements herein are true and correct to the best of his knowledge.

*Ervin Neighbors*

Subscribed and sworn to before me this 16 day of January 1989.



*Dorothy M. Hagler*  
 Notary Public

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 20 1989  
 1-20-89  
 CORRELATION DIVISION  
 Wichita, Kansas