

1 080339

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,462-0000

SW NE NE, SEC. 18, T 33 S, R 14 W/E

4290 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5476

Lease Name Cline Well # 1-18

Operator: DNB Drilling, Inc.

County Barber 159.25

Name & Address 535 North Oliver

Well Total Depth 4900 feet

Wichita, KS 67208

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1054

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:30 pm Day: 7 Month: March Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" set at 4895' PBTD 4856 Perfs at 4805-13, 4817-19, 4821-24, 4829-31, 4835-39'

1st plug sand back to 4750' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 8 sx gel, 1 sack hulls, and 125 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 pm Day: 7 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4750' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 8 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION

MAR 15 1985 3-15-85

Maximum pressure 1000 psi and shut in 900 psi

Remarks: Recovered 3292' 5 1/2" casing. Cemented by Sun Cement Co., Wichita, Kansas
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 3-18-85

Signed J. A. [Signature] (TECHNICIAN)

INV. NO. 7359

3-7