

To: 1 041148  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 007-01,042-00-01  
NW SE NW, SEC. 16, T 33 S, R 14 W XE

TECHNICIAN'S PLUGGING REPORT **2-13**  
Operator License # 5447  
Operator: OXY USA INC.  
Name & Address: 110 S. Main, Ste. 800  
Wichita, KS 67202

3355 feet from S section line  
3355 feet from E section line  
Lease Name McGrath A Well # 1  
County Barber  
Well Total Depth 5010 <sup>162.83</sup> feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 812

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_  
Plugging Contractor Clarke Corporation License Number 5105  
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9:45 a.m. Day: 13 Month: 2 Year: 1996  
Plugging proposal received from Lance Fellhoelter  
(company name) OXY USA INC. (phone) 316-672-5630

Work: 5 1/2" at 5002' w/300 sx cement, PBD 4957', Perfs at 4650-60, 3460-75'  
1st plug put 2 sx cement on CIBP at 4580',  
2nd plug sand back to 3400' and dump 5 sx cement on top of sand through bailer,  
Run 2 3/8" tubing in:  
3rd plug spot 50 sx cement at 827', 4th plug spot 50 sx cement at 410',  
5th plug spot 15 sx cement at 60'.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11 a.m. Day: 13 Month: 2 Year: 1996

ACTUAL PLUGGING REPORT 1st plug put 2 sx cement on CIBP at 4580',  
2nd plug sanded back to 3400' and dumped 5 sx cement on top of sand bridge through bailer,  
Run 2 3/8" tubing in to spot plugs:  
3rd plug at 827' with 50 sx cement,  
4th plug at 410' with 50 sx cement,  
5th plug at 60' with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2900' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 2-28-96  
INV. NO. 44902  
2-13

Signed Stephen J. Pfeifer (TECHNICIAN)

RECEIVED  
KANSAS CORP  
FEB 15 1996  
A 1133