

To: 1031352 SEP 22 1995

API NUMBER 15- 007-22,478 - 0000

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

S/2 SW SE, SEC. 20, T 33 S, R 14 W/E

330 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972

Lease Name Hoey Well # 15-20

Operator: Petroglyph Operating Co., Inc.

County Barber

Name:

Address P.O. Box 1839

Well Total Depth 4830 156.98 feet

Hutchinson, KS 67504-1839

Conductor Pipe: Size 13 3/8 feet 43

Surface Casing: Size 8 5/8 feet 1070

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co, Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 10 p.m. Day: 22 Month: 9 Year: 19 95

Plugging proposal received from Joe

(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1100' with 50 sx cement, 2nd plug at 740' with 25 sx cement,

3rd plug at 220' with 25 sx cement, 4th plug at 40-0' with 10 sx cement

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1995
9-27-95
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Durr (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 11:45 p.m. Day: 22 Month: 9 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug at 1100' with 50 sx cement,

2nd plug at 740' with 25 sx cement,

3rd plug at 220' with 25 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED
KERRY observe this plugging.

DATE SEP 10 1995

Signed Steve Durrant (TECHNICIAN)

INV. NO. 43711

9-22

FOR USE

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

EFFECTIVE DATE: 8-9-95

State of Kansas

007-22,478-0000

ALL BLANKS MUST BE FILLED

DISTRICT # 1
YEAR Yes

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date August 4, 1995
month day year

OPERATOR: License # 30972
Name: PETROGLYPH OPERATING CO., INC.
Address: P. O. Box 1839
City/State/Zip: Hutchinson, Kansas 67504-1839
Contact Person: Duane Purser
Phone: 316/665-8500

CONTRACTOR: License # 5929
Name: DUKE DRILLING CO., INC.

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... X Infield ... X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... CWMO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
If CWMO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth:
Bottom Hole Location:

Exp. 2/4/96

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with the provisions of the Kansas Conservation Commission Act, Chapter 55-1100, Kansas Statutes.

220' Basket
260' Basket
Bottom

Pusher Joe
SPUD DATE 9-13-95 INIT. DR

LENGTH SURFACE PLANNED 133' Cond 46' +
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

225SX - 275SX = 700' - 200' - 200' - 200' Kill
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 57/8 @ 207.9 CONDUCTOR 13/8 43'
ANHYDRITE T- B- ELEVATION
Loss circ. 700' - 1 5/8 13 3/8 - 900' - 200' no conf.

TD 4845 @ 1830
RAN PIPE @ 5X DV TOOL ALT II DONE SX Y N

Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
1 Anhydrite Base @ 1100 Ft. W/ 50 SX
2 1/2 Base Anyh. @ 244 Ft. W/ 25 SX
3 1/2, 1/2 Plug @ 220 Ft. W/ 25 SX
4 Bottom Surface @ 40-0 Ft. W/ 10 SX
40' Plug @ Ft. W/ SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well) Pond Hauling
TECHNICIAN SD DATE

TYPE OF CEMENT 60/40 60% 60%
STARTING TIME 10:04 (AM/PM) DATE 9-22
COMPLETION TIME 10:45 (AM/PM) DATE 9-22
CEMENT COMPANY Hall

1" to 200' - 210'
50SX - 2 hrs. 50SX - TAG 135
140 - 155SX into pit

RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1995
CONSERVATION DIVISION
Topeka, Kansas